


QUOTATION

Name of work :- Laying of G.I/ PVC pipe for cable routing at entry gate of faculty building annexe site adjacent to gate no 01 for civil counterpart accessibility with heavy loading vehicle at IIT Kanpur.

Sl.No.	Description of item	Qty.	Unit	Rate	Amount
				(In words & Figures)	
1	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
1.1	100 mm dia	60.00	Metre		
2	Providing, laying and fixing following dia PVC pipe (working pressure 4 kg / sqcm.) in ground complete with PVC fittings including trenching (75 cm deep) and re-filling etc as required.				
2.1	160 mm dia	51.00	Metre		
Total Rs.					_____


राघवेंद्र सिंह
RAGHVENDRA SINGH
अध्यापी अभियंता (वि०) E.E. (Elect.)
संविधान, भारतीय संरक्षण, क
I.I.T., Kanpur