

Quotation

Name of work :- Replacement of defective and damaged switch, sockets ,RCCB,LED tube, fittings, Fan ,exhaust etc at Gast Room,D block 6th floor R A Tower , Foot ball washroom, Office,A603 Hall-13, N-6 SBRA, F block 5 floor Hall-12, etc and other associated works.


S. No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	3 x 1.5 Sq.mm..	11.00	Mtr.		
b)	3 x 4 Sq.mm..	29.00	Mtr.		
2	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	21.00	Mtr.		
3	S & F shisham wood board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
a)	100 mm x 100 mm	1.00	Nos.		
b)	175 mm x 100 mm	5.00	Nos.		
4	S & F 40 amp to 63 amp rating 240 volts 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd. (legrand)				
a)	Triple Pole	1.00	Nos.		
5	S & F following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd.				
a)	40 Amp	2.00	Nos.		
b)	63 Amp	1.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
6	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and with lamp as required complete.				
a)	LED tube light fitting (1 X 18 / 20 Watt. LED) surface mounting luminaires wipro meke	8.00	Nos.		
b)	LED mirror light fixture 5/7/10 Watt	3.00	Nos.		
c)	12W LED surface mounted, IP20, 1200 Lumens fitting cat no. SM 250/260 Philips make.	39.00	Nos.		
7	Supply / fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make-Phillips)				
a)	LED bulb 7/10 W	9.00	Nos.		
b)	LED tube light 18 / 20 Watt.	38.00	Nos.		
8	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
a)	Bulk head fitting suitable for 60W GLS lamp, Philips make or equivalent.	2.00	Nos		
9	Installation ,Testing, Commissioning of wall bracket /ceiling fittings of all sizes and shapes containing upto two GLS/CFL/LED lamps per fitting, complete with all accessories including connections etc. as required	6.00	Nos.		
10	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
a)	1/2 module	1.00	Nos.		
b)	3 module	4.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
11	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a)	5/6 Amp switch	22.00	Nos.		
b)	15/16 Amp. switch	8.00	Nos.		
c)	3 Pin 5/6 Amp. socket outlet	8.00	Nos.		
d)	6 Pin 15/16 Amp. socket outlet.	7.00	Nos.		
e)	Telephone socket outlet	1.00	Nos.		
f)	Fan regulator socket type rotary step	20.00	Nos.		
12	S & F following piano type switch /socket on existing switch box/cover l/c connection etc as reqd.				
a)	5/6 Amp switch	22.00	Nos.		
b)	15/16 Amp. switch	7.00	Nos.		
c)	3 Pin 5/6 Amp. socket outlet	8.00	Nos.		
d)	6 Pin 15/16 Amp. socket outlet.	6.00	Nos.		
e)	Bell Push	1.00	Nos.		
f)	Fan regulator socket type rotary step	4.00	Nos.		
13	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator l/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	7.00	Nos		

S. No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
14	Supply, Installation of exhaust fan, 900 rpm 220 volt AC, 50 Hz of following sweep in the existing opening I/c connection, testing, commissioning etc as reqd.				
a)	300 mm	7.00	Nos.		
15	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	1.00	Nos.		
16	Supplying and fixing brass batten/ angle holder including connection etc. as required.	32.00	Nos.		
17	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	21.00	Nos.		
18	Supplying and fixing call bell/ buzzer suitable for D.C./A.C. single phase, 230 volts, complete as required.	4.00	Nos.		
19	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	35.00	Nos.		
20	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	4554.00	Sq.cm		
21	Dismantling and refixing of shisham wood board of any sizes on surface or in recessed etc as reqd.	8.00	Nos.		

Total Rs.


राघवेंद्र सिंह
RAGHVENDRA SINGH
 अधिशापी अधिकारी (वि०) E.E. (Elect.)
 सं० नि० वि०, मा० प्रौ० संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur

Redu