

QUOTATION


Name of work - Modification / Renovation work of electrical installation of houses no. 1028 and 188A civil maintenance office .

Description of Items	Qty	Unit	Rate	Amount
			(In words & Figures)	
1 Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.				
a) Group 'A'	20.00	Points		
2 Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a) 1 x 1.5 Sq.mm..	120.00	Mtr.		
b) 3 x 1.5 Sq.mm..	100.00	Mtr.		
c) 3 x 4 Sq.mm..	100.00	Mtr.		
d) 3 x 6 Sq.mm..	30.00	Mtr.		
3 S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a) 5/6 Amp switch	40.00	Nos.		
b) 15/16 Amp. switch	10.00	Nos.		
c) 3 Pin 5/6 Amp. socket outlet	20.00	Nos.		
d) 6 Pin 15/16 Amp. socket outlet.	10.00	Nos.		
4 Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	20.00	Nos.		
5 Supplying and fixing single pole blanking plate in the existing MCB DB complete etc. as required.	2.00	Nos.		

Description of Items	Qty	Unit	Rate	Amount
			(In words & Figures)	
6 Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
a) 6 way , Double door	1.00	Nos.		
b) 12-way , Double door	1.00	Nos.		
7 Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.				
a) Single Pole	22.00	Nos.		
8 S & F following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd.				
a) 40 Amp	2.00	Nos.		
9 Earthing with G.I earth pipe 4.5 mtr long, 40 mm dia including accessories, and providing masonary enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.	2.00	Set		
10 S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a) Fan regulator socket type rotary step	5.00	Nos.		
11 Providing and fixing casing and capping in place of defective and damaged wood batten including dismentling of betten and wire & relaying of wires as required complet.				
a) 20 x 12 mm	120.00	Mtr.		
b) 25 x 16 mm	80.00	Mtr.		
c) 32x 16 mm	50.00	Mtr.		
d) 38 x 16 mm	30.00	Mtr.		

Description of Items	Qty	Unit	Rate	Amount
			(In words & Figures)	
12 S & F wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
a) 100 mm x 100 mm	25.00	Nos.		
b) 175 mm x 100 mm	12.00	Nos.		
c) 200 mm x 150 mm	2.00	Nos.		
d) 200 mm x 250 mm	5.00	Nos.		
13 Dismantling damaged DB/TPN Switches/ loose wire boxes along with all accessories and depositing the same in the store as reqd.	2.00	Nos.		
14 Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
a) Bulk head fitting suitable for 60W GLS lamp, Philips make or equivalent.	3.00	Nos.		
15 Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	30.00	Nos.		
16 Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a) 1200 mm	5.00	Nos.		
17 S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	500.00	Sq.inch		
18 Dismantling and refixing of wooden board of any sizes on surface or in recessed etc as reqd.	20.00	Nos.		
19 Supplying and fixing of the 20W LED TUBE LIGHT with fitting (DOUBLE SIDE CONNECTION) light fixtures complete with full frame, all accessories with lamp as required complete.	5.00	Nos.		

Total Rs.


राघवेंद्र सिंह 3/2/2020
RAGHVENDRA SINGH
 अधिशासी अभियंता (वि०) E.E. ()
 स०नि०वि०, मा० प्रौ० संस्थान, क०
 I.W.D., I.I.T., Kanpur
