

QUOTATION

Subj Augmentation of capacity of CC Data center -2 by enhancing the capacity of main MCCB and circuit wires.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
				(In words & Figures)	
1	Supplying and drawing following sizes of ERLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	2 x 35 sq.mm.	75.00	Meter		
2	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
a	25/35/50 Sq.mm.	20.00	Nos.		
3	Supplying and fixing connecting and commissioning following rating, Four pole, 35kA MCCB with thermal based TMD/TMA release in the existing DB/ Box as required complete.				
a	160 A	1.00	Nos.		

Total Rs.


राघवेंद्र सिंह
RAGHIVENDRA SINGH
इलेक्ट्रिकी सर्विस (P.C.) E. E. (Elect.)
सर्विसिंग, इलेक्ट्रिकल, मरिनेट
I.V.D.
