


QUOTATION

Name of work: Replacement of damaged underground LAN wire in Houses No .203 & 205 Type-II in the campus .

S.No.	Description	Qty.	Unit	Rate <small>(In words & Figures)</small>	Amount
1	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
2	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	180.00	Mtr.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	15.00	Mtr.		
b)	25 x 16 mm	15.00	Mtr.		
4	Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	90.00	Mtr.		
b)	In pipe	10.00	Mtr.		
c)	In open duct	5.00	Mtr.		

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
d)	On surface with MS clamp	5.00	Mtr.		
5	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	300.00	Sq.cm		
6	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a)	50mm dia	10.00	Mtr.		

Total Rs


 अधिशाही अभियन्ता (वि०) / E.E. (Elect.)
 स० नि० वि०, भा० प्र० संस्थान, कानपुर
 I.W.D., I.I.T. Kanpur
