

QUOTATION

Name of work:- Repairing of HT cable of Transformer no.-1 at Substation No.4.

S.No.	Description of item	Qty	Unit	Rate	Amount
(In words & Figures)					
1	Supplying and making straight through cable jointing with heat shrinkable jointing kit complete with all accessories including ferrules suitable for following size of 3 core, XLPE aluminium conductor cable of 11 KV grade as required :				
a	120-185 sq. mm	1.00	Each		
2	Lifting removing cable exceeding 95 sq.mm. but not exceeding 185sq.mm. size from trench/clamps, making role & depositing the same in store l/c cartage.as per requirement.	10.00	Mtr		
Total Rs.					<hr/> <hr/>

Kem

प्रमाणित अधिकारी (एच) सिंह, (ए.ई.)
महो-पंडित, मन्दास रो-मार्ग, कांसू
W.D. L.L. Kanour