

QUOTATION


Name of work :- Providing Telephone points & Network points, power / plug point in main auditorium to facilitate convocation programme-2021.

| S.No | Description of Items | Qty | Unit | Rate (in words & Figures) | Amount |
|------|--|-------|------|------------------------------|--------|
| 1 | Supplying and drawing telephone cable of 2 pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required. | 80.00 | Mtr. | | |
| 2 | Supplying and fixing following piano type switch /socket on existing switch box/cover I/c connection etc as reqd. | | | | |
| a | 5/6 Amp switch | 5.00 | Nos. | | |
| b | 15/16 Amp. switch | 5.00 | Nos. | | |
| c | 3 Pin 5/6 Amp. socket outlet | 5.00 | Nos. | | |
| d | 6 Pin 15/16 Amp. socket outlet. | 5.00 | Nos. | | |
| 3 | Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd. | | | | |
| a | 5/6 Amp switch | 15.00 | Nos. | | |
| b | 15/16 Amp. switch | 10.00 | Nos. | | |
| c | 3 Pin 5/6 Amp. socket outlet | 10.00 | Nos. | | |
| d | 6 Pin 15/16 Amp. socket outlet. | 12.00 | Nos. | | |
| e | Telephone socket outlet | 6.00 | Nos. | | |

| S.No | Description of Items | Qty | Unit | Rate (in words & Figures) | Amount |
|------|---|--------|------|------------------------------|--------|
| f | Fan regulator socket type rotary step | 4.00 | Nos. | | |
| g | Blanking plate | 15.00 | Nos. | | |
| 4 | Supplying and fixing following modular base & cover plate on existing modular metal boxes etc. as reqd. | | | | |
| a | 1 or 2 module | 3.00 | Nos. | | |
| b | 3 module | 6.00 | Nos. | | |
| c | 6 module | 3.00 | Nos. | | |
| d | 8 module | 2.00 | Nos. | | |
| e | 12 module | 3.00 | Nos. | | |
| 5 | Supply and drawing PVC insulated single core cable for connection of equipments / exhaust fan & other work as reqd. | | | | |
| a | 1x2.5sqmm | 150.00 | Mtr. | | |
| b | 1x6sqmm | 24.00 | Mtr. | | |
| 6 | Drawing of optical cable enhanced cat 5/cat 6/telephone/ networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd. | 500.00 | Mtr. | | |
| 7 | Supply fixing connecting & commissioning of following rating 3 pin Plug top as reqd complete. | | | | |
| a | 5/6 Amp | 2.00 | Nos. | | |

| S.No | Description of Items | Qty | Unit | Rate (in words & Figures) | Amount |
|------|--|--------|------|------------------------------|--------|
| b | 15/16 Amp | 5.00 | Nos. | | |
| 8 | Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd. | | | | |
| a | 1200 mm | 1.00 | Nos | | |
| 9 | Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required. | | | | |
| a | 2 moduler | 6.00 | Nos. | | |
| 10 | Supplying, installation DLP mini-trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd. | | | | |
| a | Mini- trunking | 100.00 | Mtr. | | |
| b | End cap left or right | 10.00 | Nos. | | |
| c | Internal/ external angle | 25.00 | Nos. | | |
| d | Flat angle | 10.00 | Nos. | | |
| e | Flat junction | 5.00 | Nos. | | |
| 11 | Supplying, installation DLP plastic trunking 105mm x 50mm and accessories plastic trunking without cover, for trunking, covers and partitions etc. as reqd. | 30.00 | Mtr. | | |

| S.No | Description of Items | Qty | Unit | Rate | Amount |
|------|---|-------|------|------|--------|
| 12 | Supply and fixing of following accessories suitable for 105mm x 50mm size plastic trunking white system | | | | |
| a | PVC trunking full cover of size 85 mm size | 28.35 | Mtr. | | |
| b | End cap | 4.00 | Nos | | |
| c | Internal angle. | 5.00 | Nos | | |
| d | flat angle | 5.00 | Nos | | |
| e | partition junction | 2.00 | Nos | | |
| f | Base joint | 2.00 | Nos | | |
| | Total Rs | | | | |


कनिष्ठा अधिकारी (सि.) / इ.क. (सि.)
महानगर, वा. प्र. संस्थान, कांठूर
I.W.D., I.I.T. Kanpur
