


QUOTATION

Name of work:-Replacement of old and damaged LAN wire from Network hut to House No.409,439 & 4008 Type-IV in the campus.

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	6.00	Nos.		
2	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	270.00	Mtr.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	10.00	Mtr.		
b)	25 x 16 mm	20.00	Mtr.		
c)	32x 16 mm	15.00	Mtr.		
4	Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	124.00	Mtr.		
b)	In pipe	17.00	Mtr.		

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
c)	In open duct	5.00	Mtr.		
d)	On surface with MS clamp	10.00	Mtr.		
5	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a)	50mm dia	17.00	Mtr.		

Total Rs


 कर्मचारी जमानत (पि)/ए.ए. (वि.पि.)
 म.पि.वि.पि., म.पि. वि.पि. म.पि. वि.पि.
 U.W.D., I.I.T. Kanpur
