

QUOTATION

Sub:- Repairing/replacement of defective electrical items in Security Barrack Hall 4, NWTF-301, HB GF, BSBE Lab 10&11 and different labs and offices in academic area on complaint basis.

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 2.5 sq. mm	30.00	Metre		
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	15/16 A switch	10.00	No.		
b	6 pin 15/16 A socket outlet	10.00	No.		
3	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	6 Module	3.00	No.		
b	12 Module	1.00	No.		
4	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				
a	20 mm	3.00	Meter		
5	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	3.00	Meter		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
6	Dismantling, disconnecting old damaged unserviceable fl fitting/exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	9.00	Nos.		
7	Supplying and fixing following size/modules, plastic box for modular switches in recess etc as required.				
a	6 Module	3.00	Nos.		
b	12 Module	1.00	Nos.		
8	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				
a	36 watt recess mounting LED light fixture 600 x 600 mm	6.00	Nos.		
9	Supplying and fixing exhaust fan shutter for following sizes exhaust fan on rag bolts as reqd complete.				
a	for 375 mm / 15" sweep	1.00	Nos.		
10	Supply, Installation testing and commissioning of following seep, copper wound, 900 RPM, 220 volt AC, 50 Hz exhaust fan in the existing opening etc as required complete.				
a	300 mm / 12" sweep	2.00	Nos.		
b	375 mm / 15" sweep	1.00	Nos.		

SL No.	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
--------	-------------	-----	------	------------------------------	--------

11	Supply and installation of 400mm sweep AC 230/250 volts, 50 Hz wall mounting revolving fan with brackets etc complete.	1.00	Nos.		
----	--	------	------	--	--

Total Rs.



अधिसायी अमियता (वि०) E.E. (Elect.
संनिविदि, या०प्रौ० संस्थान, कानपुर
I.W.D., I.I.T., Kanpur

