

QUOTATION


Sub:- Replacement of damaged electrical items like wire, switch, socket MCB & LED lights etc in Nano science, NL-I-206, ACMS-112, NCL-107, SL-211, FB-485, & NL-II-303 etc other offices & labs in academic area on complaint basis.

| SL No. | DESCRIPTION | QTY | UNIT | RATE | AMOUNT |
|--------|---|-------|-------|----------------------|--------|
| | | | | (In words & Figures) | |
| 1 | Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required. | | | | |
| 1.01 | 3 x 1.5 sq. mm | 16.00 | Metre | | |
| 1.02 | 3 x 2.5 sq. mm | 14.00 | Metre | | |
| 1.03 | 3 x 4 sq. mm | 31.00 | Metre | | |
| 2 | Supply and fixing of 32 x 20 mm DLP mini-trunking white-system with independent cover etc. as required complete. | 12.00 | Meter | | |
| 3 | Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system. | | | | |
| 3.01 | internal / external angle | 3.00 | Nos. | | |
| 3.02 | changeable flat angle | 1.00 | Nos. | | |
| 4 | Supply, installation, testing and commissioning of following LED lamp in existing fitting as required complete. | | | | |
| 4.01 | 20 watt ESENTIAL PHILIPS or equivalent Tube in place of 36/40 W FL tube | 6.00 | Nos. | | |
| 5 | Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffuser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete. | | | | |

| SL No. | DESCRIPTION | QTY | UNIT | RATE | AMOUNT |
|--------|--|-------|------|----------------------|--------|
| | | | | (In words & Figures) | |
| 5.01 | 1 X 20W Box type LED tube with fitting | 1.00 | Nos. | | |
| 5.02 | 18 watt recess 300 x 300 mm mounting LED light fixture | 13.00 | Nos. | | |
| 5.03 | 36 watt recess mounting LED light fixture 600 x 600 mm | 6.00 | Nos. | | |
| 6 | Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. | | | | |
| 6.01 | 5/6 A switch | 6.00 | No. | | |
| 6.02 | 15/16 A switch | 4.00 | No. | | |
| 6.03 | 3 pin 5/6 A socket outlet | 4.00 | No. | | |
| 6.04 | 6 pin 15/16 A socket outlet | 4.00 | No. | | |
| 6.05 | Telephone socket outlet | 1.00 | No. | | |
| 6.06 | Blanking Plate | 1.00 | No. | | |
| 7 | Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required. | 1.00 | No. | | |
| 8 | Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required. | | | | |
| 8.01 | for 2 Module | 1.00 | No. | | |
| 8.02 | 4 Module | 1.00 | No. | | |
| 8.03 | 6 Module | 4.00 | No. | | |

9

| SL No. | DESCRIPTION | QTY | UNIT | RATE | AMOUNT |
|----------------------|---|-------|------|------|--------|
| (In words & Figures) | | | | | |
| 9 | Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required. | | | | |
| 9.01 | 1 or 2 Module | 1.00 | Nos. | | |
| 9.02 | 4 Module | 1.00 | Nos. | | |
| 9.03 | 6 Module | 4.00 | Nos. | | |
| 10 | Supply, Installation testing and commissioning of following seep, copper wound, 900 RPM, 220 volt AC, 50 Hz exhaust fan in the existing opening etc as required complete. | | | | |
| 10.01 | 375 mm / 15" sweep | 1.00 | Nos. | | |
| 11 | Supplying and fixing exhaust fan shutter for following sizes exhaust fan on rag bolts as reqd complete. | | | | |
| 11.01 | for 375 mm / 15" sweep | 1.00 | Nos. | | |
| 12 | Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store. | 19.00 | Nos. | | |
| Total Rs. | | | | | _____ |


 ३
 कर्मचारी अधिकाया / S.E.
 वाणिज्यिक (I.W/D)
 भारतीय वायुसेना, कानपुर
 I.I.T., Kanpur
