

QUOTATION

Sub: Installation of new hi wall split type AC's with associated works at Hydraulic lab & DORA Office.

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
1	Installation, testing and commissioning of following indoor and outdoor unit and other accessories from the standard pipe length i/c extra amount of refrigerant if extended pipe length upto 5.0 Mtrs in the units of following capacity complete etc. as required.				
a)	1.5 to 2.0 TR Capacity	8	No.		
2	Supply & fixing of refrigerant copper piping for suction & discharge line .as per standard specification with insulation on surface / recessed with clamps, screws complete from indoor to out door units complete etc as reqd.				
a)	1.5 to 2.0 TR Capacity	51	Mtr		
3	Supply & fixing of 25 mm dia PVC drain pipe heavy duty ISI marked or flexible pipe for insulated drain line with accessories with clamps on surface / recessed etc. and as reqd.	47	RMT		
4	Supply, fixing & connecting of following core power supply control copper cable of approved make complete as reqd.				
a)	3 / 4 core control cable	72	Mtr		
5	Supply & fixing of Angle iron frame made of 25/32 mm, thickness 5 mm for mounting of outdoor unit size, duly painted and finished with cage and GI/ fiber canopy and vibration isolation pad if required complete etc. as reqd.				
a)	Wall mounted (Upto 2.0 TR Capacity)	8	No.		

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
6	Supplying & installation of DLP trunking 105 x 50mm and accessories plastic trunking without cover and partitions etc as reqd.	17	Mtr		
7	Supplying & installation of flexible cover 85 mm for DLP trunking size 105mm x 50mm etc as reqd.	17	Mtr		

Total Rs. _____



विनय कुमार तिवारी
VINAY KUMAR TIWARI
अधियक्षक अलिखता (वा.) E.E. (A.C.)
संयोजक, नरूपी संस्थान, काभूर
I.W.O., I.L.T., Kanpur