

**INDIAN INSTITUTE OF TECHNOLOGY KANPUR
INSTITUTE WORKS DEPARTMENT
ELECTRICAL & AIR-CONDITIONING DIVISION**

No. 01/AC/EE/2019/41

Dated 24-04-2019

QUOTATION NOTICE

M/s

.....

.....

.....

Dear Sirs,

Sealed quotations are invited from the empanelled contractors/specialized agency by the undersigned on behalf of the Director, IIT Kanpur for **“Supply, installation, testing & commissioning of Hi wall split type air conditioner units of 1.5 TR Capacity at W.L.Ext.-302.”** As per enclosed Bill of Quantity/ overleaf, so as to reach in this office on or before 09-05-19 upto 3.00 PM and the quotation will be opened on the same day at 3.30PM in the presence of quotationers or their representative who want to be present.

The terms and conditions of the quotation are as under:


1. The quotations should be submitted in a properly sealed envelop, addressed to the undersigned. The enquiry nos. and date should invariably quoted on the top of the envelop.
2. The time allowed for carrying out the above noted work is 21(Twenty One) Days.
3. The rates quoted should be exclusive of GST, no other tax is payable except GST. GST shall be applicable as per Govt. norms..
4. Security @ 10% shall be deducted from the bills which shall be released on successful completion of defect liability period of six months.
5. The estimated cost of quotation is **Rs.51,774/-**. The required earnest money of **Rs. 1035/-** is to be submitted in the form of FDR pledged in favour of the Director, IIT Kanpur alongwith the quotation. The earnest money of the unsuccessful quotationers will be returned within one month's time.
6. The quotations shall remain valid for 90 days from the date of opening.
7. Income tax will be recovered as per notification of Government from the bill and the amount so recovered will be deposited in the State Bank of India at the credit of the firm.
8. The earnest money/Security deposit will be regulated as per the norms of C.P.W.D.
9. The Institute reserves the right of accepting or rejecting any quotations without assigning any reason thereof.
10. The material should be used as per approved list of make.

QUOTATION

Sub: Supply, installation, testing & commissioning of Hi wall split type air conditioner units of 1.5 TR Capacity at W.L.Ext.-302.

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
1	Supply, installation, testing & commissioning of Hi wall split type of following capacity inverter model, of approved make, with/without digital display in ID unit with remote and other accessories complete with ID and OD unit with copper condensing unit, R-410 refrigerant etc complete as reqd.				
a)	1.5 TR capacity, nominal 5 star rated	1.00	No.		
2	Supply & fixing of additional refrigerant copper piping for suction & discharge line .as per standard specification with insulation on surface / recessed with clamps, screws complete from indoor to out door units complete etc as reqd.				
a)	Refrigerant pipe diameter 6.35 mm / 15.88 mm	5.00	RMT		
3	Supply & fixing of 25 mm dia PVC drain pipe heavy duty ISI marked or flexible pipe for insulated drain line with accessories with clamps on surface / recessed etc. and as reqd.	5.00	RMT		
4	Supply & fixing of Angle iron frame made of 25/32 mm, thickness 5 mm for mounting of outdoor unit size, duly painted and finished with canopy and vibration isolation pad if required complete etc. as reqd.				
a)	Upto 2.0 TR capacity (Wall/Floor mounted)	1.00	No.		
5	Supply, fixing & connecting of 4 core, 4 sqmm power supply control copper cable of approved make complete as reqd.	5.00	RMT		

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
6	Supplying & installation of DLP trunking 105 x 50 mm and accessories plastic trunking without cover and partitons etc. as reqd.	3.00	RMT		
7	Supplying & installation of flexible cover 85 mm for DLP trunking size 105 mm x 50 mm etc as reqd.	3.00	RMT		


 अधीक्षक अभियंता (सह) E.E. (A.C.)
 संचालक, माओवादी संस्थान, काठपुर
 L.W.D., L.I.T., Kasper