

INDIAN INSTITUTE OF TECHNOLOGY KANPUR  
INSTITUTE WORKS DEPARTMENT  
ELECTRICAL & AIR-CONDITIONING DIVISION

No. 07/AC/EE/2019/75

Dated 27.05.2019

QUOTATION NOTICE

M/s .....

Dear Sirs,

Sealed quotations are invited from the empanelled contractors/specialized agency by the undersigned on behalf of the Director, IIT Kanpur for "**Half body fabrication of water coolers and other associated works in different location in Hall-I, III, V, BSBE, CESE etc. and installation of split AC's/ water coolers at CESE-217,, WLE-Ext-302"A", cyber security cell & techkriti etc..**" As per enclosed Bill of Quantity/ overleaf, so as to reach in this office on or before 04-06-19 upto 3.00 PM and the quotation will be opened on the same day at 3.30PM in the presence of quotationers or their representative who want to be present.

The terms and conditions of the quotation are as under:

1. The quotations should be submitted in a properly sealed envelop, addressed to the undersigned. The enquiry nos. and date should invariably quoted on the top of the envelop.
2. The time allowed for carrying out the above noted work is 28(Twenty Eight) Days.
3. The rates quoted should be exclusive of GST, no other tax is payable except GST. GST shall be applicable as per Govt. norms..
4. Security @ 10% shall be deducted from the bills which shall be released on successful completion of defect liability period of six months.
5. The estimated cost of quotation is **Rs.1,00,865/-**. The required earnest money of **Rs. 2017/-** is to be submitted in the form of FDR pledged in favour of the Director, IIT Kanpur alongwith the quotation. The earnest money of the unsuccessful quotationers will be returned within one month's time.
6. The quotations shall remain valid for 90 days from the date of opening.
7. Income tax will be recovered as per notification of Government from the bill and the amount so recovered will be deposited in the State Bank of India at the credit of the firm.
8. The earnest money/Security deposit will be regulated as per the norms of C.P.W.D.
9. The Institute reserves the right of accepting or rejecting any quotations without assigning any reason thereof.
10. The material should be used as per approved list of make.

## QUOTATION

**Sub: Half body fabrication of water coolers and other associated works in different location in Hall-I, III, V, BSBE, CESE etc. and installation of split AC's/ water coolers at CESE-217,, WLE-Ext-302"A", cyber security cell & techkriti etc.**

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
1	Half body fabrication of water cooler body 150/150 Ltrs capacity 18 Gauge/20 Gauge GI sheet with base frame duly painted and complete in all respect complete as reqd.	5.00	Nos		
2	Supply and fixing of base plate/ angle iron frame (with provision of fixing compressor, condenser unit & motor etc.) of water cooler up to 150 Litrs.capacity (i/c. removing & fixing of all spares) as reqd. (complete).	8.00	Nos		
3	Supply and fixing condenser unit housing for water cooler of 150 Litrs.capacity of size as reqd. (complete).	10.00	Nos		
4	Spray painting of water cooler 150 litres capacity Freezer/ Deep freezer 300/ 400 Ltr capacity after denting work of small patches, scurbbing old paint, painting with one coat of primer and two coat of super enamel paint of approved brand manufacture as required.	8.00	Nos		
5	Providing & fixing of water purifier with additional pre-filter etc. complete as reqd.	2.00	Nos.		
6	Installation, testing & commissioning of water cooler (storage type ) fully stainless steel of 150/150 litres model with all accessories. The work includes PVC connection, control cable with plug top, drain pipe by making hole and chase cutting wherever it required as per site and repair the same with original finish etc as reqd.	3.00	Nos.		

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
7	Installation, testing and commissioning of following indoor and outdoor unit and other accessories from the standard pipe length i/c extra amount of refrigerant if extended pipe length upto 5.0 Mtrs in the units of following capacity complete etc. as required.				
a)	1.5 to 2.0 TR Capacity	2.00	Nos.		
8	Dismantalling & removing of old water cooler of following size and shifting it to the desired location etc complete as reqd.	2.00	Nos.		
9	Supplying & installation of DLP trunking 105 x 50 mm and accessories plastic trunking without cover and partitions etc as reqd.	2.33	Mtrs		
10	Supplying & installation of flexible cover 85 mm for DLP trunking size 105mm x 50mm etc as reqd.	2.33	Mtrs		
11	Servicing of following equipment (i.e.- dismantaling ,cleaning, lubricating, re-fitting,testing & commissioning the unit) with cleaning the filters, cooling & condensing coils by removing dust, washing with approved condenser coil cleaner & finally wash with fresh water, lubricating the fan motor , denting work & painting of window ac, i/c. refitting of window ac by using auto wire,pvc tape,thimbles,m/c screws,washers,nut ,bolts, etc.as required (complete).				
a)	Split AC Upto 2.0 TR Capacity	1.00	No.		
b)	Water Cooler above 150/150 Ltrs	1.00	No.		

**TOTAL**