


QUOTATION

Name of Work: Replacement of defective and damaged cable, LED light fittings, pole box, Feeder pillar etc at outreach, drum composting site-1, IWD office etc. and other associated works.

S.No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
1	Supplying and fixing 30 amps, 415 volts, TPN industrial type, socket outlet, with 4 pole and earth, metal enclosed plug top alongwith 30 amps "C" curve, TPMCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	1.00	Nos.		
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	4 X 10 Sq.mm	4.00	Mtr		
3	Supply and drawing PVC insulated following size round cable of following size for connection of equipments / exhaust fan & other work as reqd.				
a	4 core X 2.5 Sq. mm	53.00	Mtr		
b	3 core X 1.5 Sq. mm	25.00	Mtr		
4	S & F 25 mm size of steel flexible pipe alongwith the accessories on surface etc as required.	3.00	Mtr		
5	making masonry piller of size 450mmx450mmx600mm hight above the ground level with bricks cement and send duly plastered on all sides. as reqd.	24.00	Nos.		
6	Supplying,fixing,testing commissioning of energy saving, environmental friendly,long life,exclusive innovative die cast aluminium IP 65 with high poer LEDs as light source. following LED flood light make Havells, having symmetric optics or its equivalent, on the existing pole complete as required.				
a)	70W LED flood light lamp Ca. no.JETA PROPLUSFL70WLED757LT G make Havells or it's equivalent	1.00	Nos.		

S.No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
7	Supply and installation testing and commissioning of 12W LED surface mounted, IP20, 1200 Lumens colour temperature 6500 K, with metallic CRCA powder coated housing cover highefficiency diffuser, THD less than10, power factor above 0.9. cat no. SM 250/260 Philips make or equivalent .	20.00	Nos.		
8	Dismantling conciled & damaged DB/TPN Switches/starter/ loose wire boxes along with all accessories and depositing the same in the store repairing the damages as reqd complete.	24.00	Nos.		
9	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	20.00	Nos.		
10	S&F, connecting and commissioning looping type cable end control box with SINTEX PVC box (GSJB- 2525) of size 250 mm x 200 mm x 100 mm having 1 no. 6amp to 32 amp SPMCB 250 volt and 2 nos. brass neutral link 12.5 mm square rod 6 way approx. 60 mm long and panel key type lock side door etc. complete as required.	24.00	Nos.		

Total Rs.


 राघवेंद्र सिंह
 RAGHVENDRA SINGH
 सहायक अभियंता (वि) E.E. (Elect)
 सड़क विभाग, राष्ट्रीय राजमार्ग, काठमांडू
 Q.W.D., K.I.T., Kaspur