

## QUOTATION

Sub: Replacement of damaged piece of cable feeding to roof top of WLE Building from DG set at DG House No.1.

S.N.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for 3-1/2 X 185 sqmm PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.	2.00	Nos.		
2	Supply & laying of one no. PVC insulated and PVC sheathed aluminium conductor steel armoured cable of size 3-1/2 x 185 Sqmm grade 1.1 kV as reqd.				
a	In ground i/c excavation sand cushioning protective covering, refilling of earth as reqd.	35.00	Mtr.		
b	In existing open duct.	5.00	Mtr.		
3	Digging cable trench, lifting bricks & cable for locating fault. Refilling the trench, remaining & making good the same as reqd.	10.00	Mtr.		

Total Rs. \_\_\_\_\_

  
RACHIVENDRA SHINHA  
अभिनेता, कलाकार (मि) ए. ए. (फैक्ट)  
महाराष्ट्र, मुंबई, महाराष्ट्र, भारत  
Saw