

QUOTATION

Sub: Providing 5 KVA UPS points for network rack and laying of uplink networks cable in New tinkering Lab.

S.N.	Description	Qty.	Unit	Rate(Rs.) (in Figures & words)	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	3 X 2.5 Sq.mm	150.00	Mtr		
2	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as reqd.				
a	20 mm	40.00	Mtr		
b	25 mm	180.00	Mtr		
3	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.	50.00	Mtr.		
4	Supply and fixing of following items for plastic trunking accessories suitable for size 32 mm x 20 mm				
a	End cap	2.00	Nos.		
b	Internal angle/ External angle	3.00	Nos.		
c	Changeable flat angle	2.00	Nos.		
d	Flat Junction	1.00	Nos.		
5	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	3 pin 5/6 amps socket outlet	1.00	Nos.		

S.N.	Description	Qty.	Unit	Rate(Rs.) (in Figures & words)	Amount
b	Blanking Plate	2.00	Nos.		
6	Supplying and fixing following Modular GI/plastic base & cover plate on existing modular metal boxes/DLP plastic trunking etc. as required.				
a	3 Module	1.00	Nos.		
7	Drawing of computer network cable/ PVC insulated flexible cooper/ Aluminium single core cable of size 1.5sqmm to 25 sqmm/ telephone cable upto 10 pair in existing pipe / casing and capping as reqd including numbering the wires at both the ends.	379.00	Mtr.		
TOTAL					


 राघवेंद्र सिंह
RAGHVENDRA SINGH
 अधिकायी अभियंता (वि०) E.E. (Elect.)
 संवि०वि०, भा०प्रौ० संस्था, कानपुर
 P.W.D., I.I.T., Kanpur