


## QUOTATION

Name of work: Replacement of damaged service cable of C block at VH Extension.

S. No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
1	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a	3½ X 25 sq. mm (28mm)	2.00	Nos.		
2	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a	50 mm dia	4.00	Mtr.		
3	Supplying & Laying of one no. XLPE sheathed aluminum conductor steel armoured power cable of size 3-1/2x25 sq.mm. 1.1kV grade in following manners.				
a	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	40.00	Mtr.		
b	In pipe	4.00	Mtr.		
c	In open duct	1.00	Mtr.		
d	On surface with MS clamp	5.00	Mtr.		
4	Locating fault in the cable lines with meggar etc and rectifying removing & restoring the same and making good the damages etc as required.	1.00	Nos.		

Total Rs. \_\_\_\_\_

  
RAGHVENDRA SINGH  
अविभागी अमिचला (वि.) E.E. (Elect.)  
संविधि, भाग्यी संस्थान, कानपुर  
I.W.D., I.I.T., Kanpur