

Quotation


Name of work: Electrical maintenance work at north side residence as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	3 x 1.5 Sq.mm..	1.00	Mtr.		
b)	3 x 4 Sq.mm..	6.91	Mtr.		
2	S & F following piano type switch /socket on existing switch box/cover l/c connection etc as reqd.				
a)	5/6 Amp switch	19.00	Nos.		
b)	2 way 5/6 amp switch	1.00	Nos.		
c)	15/16 Amp. switch	4.00	Nos.		
d)	3 Pin 5/6 Amp. socket outlet	4.00	Nos.		
e)	6 Pin 15/16 Amp. socket outlet.	3.00	Nos.		
f)	Call bell push	6.00	Nos.		
3	Supplying and fixing brass batten/ angle holder including connection etc. as required.	11.00	Nos.		
4	Supplying and fixing call bell/ buzzer suitable for D.C./A.C. single phase, 230 volts, complete as required.	4.00	Nos.		
5	Supplying and fixing 5 amps to 32 amps rating, 240 volts, 'C' series, MCB suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as reqd.				
a)	Single Pole	1.00	Nos.		

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
6	S & F following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd.				
a)	40 Amp	1.00	Nos.		
b)	63 Amp	3.00	Nos.		
7	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	Fan regulator socket type rotary step	6.00	Nos.		
8	Laying UTP/ RJ-11/ RJ-6/ Telephone wire/ cable in existing steel conduit pipe/ GI pipe/ HDPE pipe as reqd. (The cost shall also include numbering of networking wire from room to rack as reqd.)	30.00	Mtr.		
9	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	4.50	Mtr.		
b)	32x 16 mm	3.22	Mtr.		
10	S & F wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
a)	175 mm x 100 mm	4.00	Nos.		
11	Supply / fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make- Phillips)				
a)	LED tube light 18 / 20 Watt.	1.00	Nos.		
12	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	22.00	Nos.		
13	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	7.00	Nos		

S.No.	Description	Qty.	Unit	Rate	Amount
(In words & Figures)					
b)	1400 mm	3.00	Nos.		
14	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	600.00	Sq.cm		
15	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	11.00	Nos.		
16	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	2.00	Nos.		
17	Dismantling and refixing of wooden board of any sizess on surface or in recessed etc as reqd.	7.00	Nos.		
18	Dismantling & refixing of any size fan from normal height				
a)	ceiling fan	7.00	Nos.		

Total Rs


 रघुवेंद्र सिंह
RAGHVENDRA SINGH
 अधिसूचकी अभियंता (वि.) E.E. (Elect.)
 संविधिक, भाद्रप्रद संस्वाच, कानपुर
 W.D., I.I.T., Kanpur