

Quotation

Name of work: Electrical Maintenance work at south side residences as per enclosed complaints.

S.No.	Description	Qty.	Unit	Rate (in Words & figures)	Amount
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.				
a	Group 'A'	4.00	points		
2	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a	1 x 1.5 Sq.mm..	25.00	Mtr.		
b	3 x 1.5 Sq.mm..	20.00	Mtr.		
c	3 x 4 Sq.mm..	35.00	Mtr.		
3	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.				
a	25 mm	20.00	Mtr.		
4	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a	5/6 Amp switch	25.00	Nos.		
b	2 way 5/6 A switch	5.00	Nos.		
c	15/16 Amp. switch	9.00	Nos.		
d	3 Pin 5/6 Amp. socket outlet	5.00	Nos.		
e	6 Pin 15/16 Amp. socket outlet.	7.00	Nos.		
f	Bell push	5.00	Nos.		

S.No.	Description	Qty.	Unit	Rate (in Words & figures)	Amount
5	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 Amp. switch	7.00	Nos.		
b	15/16 Amp. switch	3.00	Nos.		
c	3 Pin 5/6 Amp. socket outlet	3.00	Nos.		
d	6 Pin 15/16 Amp. socket outlet.	1.00	Nos.		
e	Bell push	1.00	Nos.		
6	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	1.00	Nos.		
7	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required	2.00	Nos.		
8	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				
a	1 or 2 Module	1.00	Nos.		
a	3 Module	1.00	Nos.		
b	8 Module	1.00	Nos.		
9	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc. as reqd.	3.00	Nos.		
10	Supplying and fixing brass batten/ angle holder including connection etc. as required.	6.00	Nos.		
11	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	5.00	Nos.		
12	Drawing of optical cable enhanced cat5/cat6/telephone/networking/power cable in existing steel conduit pipe/GI/HDPE pipe including numbering of networking wire from room to rack as reqd.	60.00	Mtr.		
13	S & F wood board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				

S.No.	Description	Qty.	Unit	Rate (in Words & figures)	Amount
a	100 mm x 100 mm	6.00	Nos.		
b	175 mm x 100 mm	8.00	Nos.		
c	200 mm x 150 mm	1.00	Nos.		
d	200 mm x 250 mm	1.00	Nos.		
14	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a	20 x 12 mm	20.00	Mtr.		
b	25 x 16 mm	30.00	Mtr.		
c	32x 16 mm	2.00	Mtr.		
15	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a	Fan regulator socket type roatary step	4.00	Nos.		
16	Dismantling and refixing of wood board of any size on surface or in recessed etc as reqd.	10.00	Nos.		
17	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	300.00	Sq.inch		
18	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	40.00	Nos.		
19	Supply / fixing of following LED bulb in existing fitting as reqd.				
a	7 W	1.00	Nos		
20	Repairing , cleaning, testing & commissioning box /industiral type /decorative type fitting I/c replacement of all parts if reqd.	2.00	Nos.		
21	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	23.00	Nos.		
22	Supplying of 20W LED TUBE LIGHT (DOUBLE SIDE CONNECTION) lamp for fixing in existing street light fitting complete as required.	2.00	Nos.		

S.No.	Description	Qty.	Unit	Rate	Amount
				(in Words & figures)	
23	Dismantling, and refixing all type fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	4.00	Nos.		
24	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a	1200 mm	3.00	Nos.		

Total Rs


 राघवेंद्र सिंह
RAGHVENDRA SINGH
 अधिशाही अभियंता (वि०) E.E. (Elect.)
 स०नि०वि०, भा०श्री० संस्थान, काभपुर
 I.W.D., I.I.T., Kanpur