

QUOTATION

Name of work: Modification of electrical installation vacate house no. 460.

S. No	Description of Items	Qty	Unit	Rate (Rs.)	Amount
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	1 x 1.5 Sq.mm..	60.00	Mtr.		
b)	3 x 1.5 Sq.mm..	30.00	Mtr.		
c)	3 x 4 Sq.mm..	40.00	Mtr.		
2	Laying UTP/ RJ-11/ RJ-6/ Telephone wire/ cable in existing steel conduit pipe/ GI pipe/ HDPE pipe as reqd. (The cost shall also include numbering of networking wire from room to rack as reqd.)	150.00	Mtr.		
3	Supply and fixing of following sizes of medium class PVC conduit along with the accessories in surface /recess including cutting the wall and making good the same in case of recessed conduit as reqd.				
a)	25mm	25.00	Mtr		
4	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	30.00	Mtr.		
b)	25 x 16 mm	35.00	Mtr.		
c)	32x 16 mm	30.00	Mtr.		
5	S & F wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
a)	100 mm x 100 mm	15.00	Nos.		
b)	175 mm x 100 mm	6.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate (Rs.)	Amount
6	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
a)	Bulk head fitting suitable for 60W GLS lamp, Philips make or equivalent.	4.00	Nos		
7	S & F following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
a)	5/6 Amp switch	10.00	Nos.		
b)	15/16 Amp. switch	3.00	Nos.		
c)	3 Pin 5/6 Amp. socket outlet	10.00	Nos.		
d)	6 Pin 15/16 Amp. socket outlet.	3.00	Nos.		
e)	Fan regulator socket type rotary step	5.00	Nos.		
8	Supplying and fixing brass batten/ angle holder including connection etc. as required.	5.00	Nos.		
9	Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.				
a)	1200 mm	3.00	Nos		

Total Rs.


 11/1/19
 [Faint pink stamp text]
