

QUOTATION

Sub: Repairing and Replacement of defective electrical items in Air Quility Lab-R1 Sadan Block, SIDBI, Air Strip, Transport Engineering Lab, and different labs and offices in academic area on complaint basis.


S.N.	Description	Qty.	Unit	Rate(In Rs.)	Amount
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
a	Group 'C'	8.00	Nos.		
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	3 X 1.5 Sq.mm	40.00	Mtr		
b	3 x 4 Sq.mm	3.00	Mtr		
3	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.	20.00	Mtr.		
4	Providing and fixing DLP plastic trunking of size 105 mm x 50 mm without cover on surface as reqd.	1.00	Mtr.		
5	Supply and fixing of following items for plastic trunking accessories suitable for size 100 mm x 50 mm.				
a	End cap	2.00	Nos.		
6	Supplying and fixing of 32 mm dia X 2.00 metres long G.I. pipe (medium class) bracket for mounting of fluorescent / HPMV / HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, b	1.00	Nos.		
7	Supplying and fixing following of size/modules, GI box along with modular base & cover plate for modular switches in recess etc as reqd.				
a	12 module (200mm x 150mm)	1.00	Nos.		

S.N.	Description	Qty.	Unit	Rate(In Rs.)	Amount
8	Supplying and fixing following piano type switch/socket on the existing switch box/cover including connections etc as reqd.				
a	5/6 amps switch	1.00	Nos.		
9	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	5/6 amps switch	13.00	Nos.		
b	3 pin 5/6 amps socket outlet	5.00	Nos.		
10	Supplying and fixing following Modular GI/plastic base & cover plate on existing modular metal boxes/DLP plastic trunking etc. as required.				
a	1 or 2 Module		Nos.		
		2.00			
b	3 Module		Nos.		
		1.00			
c	6 Module		Nos.		
		1.00			
11	Supplying and fixing following Module Plastic box for fixing modular switches/sockets in surface/recess etc as required.				
a	1or 2Module		Nos.		
		2.00			
b	3 Module		Nos.		
		1.00			
12	Supply & retrofitting 18 watt LED PLL lamp in existing fitting and connection etc.as reqd	6.00	Nos.		
13	Supply & retrofitting 1 x 20 watt Tube LED lamp in existing fitting and connection etc.as reqd	12.00	Nos.		
14	S/F, connecting and commissioning 12 watt surface mounting LED light fixture Make Philips Star Surface or its equivalent approved make.	30.00	Nos.		

S.N.	Description	Qty.	Unit	Rate(In Rs.)	Amount
15	Supplying and fixing, 50 Watt LED FLOOD LIGHT luminaries with pressure die cast aluminium housing IP65 complete with all accessories complete (Cat No. LFLE-50-CDL Crompton Make or approved equivalent makes	2.00	Nos.		
16	S/F, connecting, testing and commissioning 1 x 20 watt LED tube fitting surface mounting/ceiling suspended luminares suitable mounting rail for T-LED lamps with 1 No. 18/20 watt T-LED lamps (Polycarbonate) and connection etc.as reqd	1.00	Nos.		
17	S/F, connecting, testing and commissioning 2 x 18/20 watt LED tube fitting surface mounting/ceiling suspended luminares suitable mounting rail for T-LED lamps with 2 No. 18/20 watt T- LED lamps (Polycarbonate) and connection etc.as reqd	4.00	Nos.		
18	S/F, connecting, testing and commissioning 18 watt LED surface mounted luminares with diffuser suitable for modular ceiling/POP/Gypsem ceiling	10.00	Nos.		
19	Supplying and fixing, 24 Watt LED street light luminaries with pressure die cast aluminium housing IP66 complete with all accessories complete	2.00	Nos.		
20	Alteration of internal wiring in existing fitting of any type for retrofitting of tube LED i/c dismantling & refixing as reqd.	5.00	Nos.		
21	S & F of following size of steel flexible pipe alongwith the accessories on surface etc as required.				
a	25 mm	5.00	Mtr.		
22	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	2.00	Nos.		
23	Supply fixing connecting & commissioning of 5 Amp. 3 pin Plug top as reqd.	2.00	Nos.		
24	Supply, Installation, testing & commissioning of Ceiling fan of following 220 volts 50 Hz without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sqmm PVC insulated copper conductor single core cable etc as reqd.				

S.N.	Description	Qty.	Unit	Rate(In Rs.)	Amount
a	1200 mm sweep	2.00	Nos		
25	Dismantling of ceiling fan / rally fan / all type fitting without regulator I/c depositing in store etc as reqd.	3.00	Nos.		
26	S & F 3 mm thick phenolic laminated sheet on existing board with brass screw & cup washer etc as reqd.	112.00	Sq.in.		
27	Supplying & fixing following size of medium class GI pipe on surface with MS clamps/in recessed i/c cutting the wall/floor & making good the same in case of recessed pipe as reqd.				
a	32 mm dia	3.00	Mtr		
28	Dismantling the old conduit pipe/wood batten of all sizes from surface/recessed & making good the damages I/c filling the holes of the surface etc as reqd.	10.00	Mtr.		
29	Supplying and fixing 3 pin, 5 amp. Ceiling rose on the existing junction box/ wooden block including connection etc as required.	4.00	Nos.		

Total Rs.


14/01/2019.

राघवेन्द्र सिंह
RAGHVENDRA SINGH
अधिकाधी अमरसता (वि०) E.E. (Elect.)
संनिविदा, मायासंस्थान, काणपुर
I.W.D., I.L.T., Kanpur