


QUOTATION

SUB: Providing earthing and network connection and KWHmeter in Shiru Café near academic area gate no.2.

S.N.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supplying and making end termination with brass compression gland with aluminium lugs for following size of PVC insulated & PVC sheathed/XLPE aluminium cable of 1.1kV grade as reqd.				
a	3-1/2x35 sqmm	2.00	Nos.		
2	Laying of one no. PVC insulated, PVC sheathed/XLPE power cable of 1.1kV grade of size Upto 35 sq. mm				
a	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	40.00	Mtr.		
b	Fixing on surface with MS clamp	15.00	Mtr.		
c	In pipe	5.00	Mtr.		
d	In open duct	5.00	Mtr.		
3	Earthing with GI earth electrode 50mm dia x 3 mtr length including earth enhancing compound (Jam Fill quality product) and PIT cover for earthing pit etc as reqd. (193GI JMV)	2.00	Set		
4	Providing & fixing 25mm x 5mm GI strip on surface or in recessd for connection etc. as reqd.	5.00	Mtr		
5	Providing and fixing following rating and breaking capacity four pole 415V 50Hz MCCB in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc as required.				
a	125 Amp, 25KA	1.00	Nos.		
6	S&F connecting and commissioning independent mounting of 125 amp MCCB enclosure make legrand or its equivalent approved make in surface/recess I/c cutting the wall and making good the same in case of recessed as reqd.	1.00	Nos.		

S.N.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
7	Supply & Laying of 32 mm (6Kg / cm ²) HDPE pipe ISI mark of 2mm thick I/c cartage loading & unloading etc. as reqd.				
a	In ground i/c excavation sand cushioning protective covering, refilling of eath as reqd.	30.00	Mtr.		
b	Fixing on surface with MS clamp	7.00	Mtr.		
8	Drawing of computer network cable in existing pipe / casing and capping as reqd including numbering the wires at both the ends.	240.00	Mtr.		
9	Fixing, Internet Box of size 75mm x 75mm x 40 mm including brass screw on surface / recessed as reqd.	3.00	Nos.		
10	Supplying, fixing, connecting, testing & commissioning of LCD display , direct operated,10-60A, kWH electronic meter 3ph 4W Kwh 10-60A cat no.TPPL1510000002OCN0 (HPL make) with Transparent hinge type box i/c sealing the same (sealing material will be supplied by the dept.) etc. as reqd.	1.00	Nos.		

Total Rs.


राघवेन्द्र सिंह
RAGHVENDRA SINCH
 अधिशाषी अभियंता (वि०) E.E. (Elect.)
 सं० नि० वि०, मा० प्रौ० संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur

R. Singh