


## QUOTATION

**Sub:** Providing electrical items in NCL, AIC, HB Electronic Room GF, WL-116 and different labs and offices in academic area on complaint basis.

S.N.	Description	Qty.	Unit	Rate ( In Words & Figures)	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	3 X 1.5 Sq.mm	6.00	Mtr		
b	3 X 2.5 Sq.mm	15.00	Mtr		
2	Supply and drawing PVC insulated copper conductor (Flexible) 3 core round cable 2.5 Sq.mm for connection of equipments / exhaust fan/AC & other work as reqd.	15.00	Mtr.		
3	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.	13.00	Mtr.		
4	Supplying and fixing following piano type switch/socket on the existing switch box/cover including connections etc as reqd.				
a	15/16 amps switch	12.00	Nos.		
b	6 pin 15/16 amps socket outlet	12.00	Nos.		
5	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	5/6 amps switch	1.00	Nos.		
b	15/16 amps switch	2.00	Nos.		
c	3 pin 5/6 amps socket outlet	1.00	Nos.		
d	6 pin 15/16 amps socket outlet	2.00	Nos.		
e	Blanking Plate	1.00	Nos.		
6	Supplying and fixing following Modular GI/plastic base & cover plate on existing modular metal boxes/DLP plastic trunking etc. as required.				

S.N.	Description	Qty.	Unit	Rate ( In Words & Figures)	Amount
a	1 or 2 Module		Nos.		
		2.00			
b	3 Module		Nos.		
		2.00			
7	Supplying and fixing following Module Plastic box for fixing modular switches/sockets in surface/recess etc as required.				
a	1 or 2 Module		Nos.		
		2.00			
b	3 Module	2.00	Nos.		
8	S & F shisham wood board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
a	200 mm x 300 mm	3.00	Nos.		
9	Supply fixing connecting & commissioning of 5 Amp. 3 pin Plug top as reqd.	1.00	Nos.		
10	Supply fixing connecting & commissioning of 15 Amp. 3 pin Plug top as reqd.	4.00	Nos.		
11	Dismantling & refixing DB/TPN Switches upto 100A/ loose wire boxes/ M.S. boxes alongwith all accessories etc as reqd.	6.00	Nos.		
12	Supply,Installation of exhaust fan 220 volt, 50 Hz of following sizes in the existing opening I/c connection, testing, commissioning etc as reqd.				
a	450 mm	2.00	Nos.		
13	S/F, Exhaust fan shutter of following sizes on rag bolts as reqd.				
a	450 mm	1.00	Nos.		

Total Rs.

  
 राघवेंद्र सिंह  
 RAGHVENDRA SINGH  
 अविधानी अभियंता (वि.) E.E. (Elect.)  
 कर्मचारी, आर.पी.एस. कक्षा, काँग्रेस  
 Sd/- W.D., I.T., Kanpur