

QUOTATION


SUB: Renovation of electrical items in FB-462 4th floor, Chemical Engineering Department

S.N.	Description	Qty.	Unit	Rate (In Words & Figures)	Amount
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
a	Group 'C'	3.00	Nos.		
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/PVC conduit as reqd.				
a	3 X 1.5 Sq.mm	12.00	Mtr		
b	3 X 2.5 Sq.mm	40.00	Mtr		
c	2 X 4 Sq.mm	15.00	Mtr		
3	Supply and drawing PVC insulated copper conductor (Flexible) 3 core round cable 2.5 Sq.mm for connection of equipments / exhaust fan/ AC & other work as reqd.		Mtr.		
a	2 Pair	30.00	Mtr		
4	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.	50.00	Mtr.		
5	Providing and fixing DLP plastic trunking of size 105 mm x 50 mm without cover on surface as reqd.	6.80	Mtr.		
6	Providing and fixing 85 mm width flexible cover of DLP plastic trunking. (size 105 mm x 50 mm.)	6.00	Mtr.		
7	Supply and fixing of following items for plastic trunking accessories suitable for size 105 mm x 50 mm.				
a	End cap	4.00	Nos.		
b	Internal angle.	1.00	Nos.		

S.N.	Description	Qty.	Unit	Rate (In Words & Figures)	Amount
8	Supplying and fixing following of size/modules, GI box along with modular base & cover plate for modular switches in recess etc as reqd.				
a	6 module (200mm x 75mm)	7.00	Nos.		
9	S/F, connecting, testing and commissioning 34/35/36 watt LED recess mounted luminaires with diffuser suitable for 600 mm X 600 mm modular POP/Gypsem ceiling etc.as reqd.	2.00	Nos.		
10	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	5/6 amps switch	9.00	Nos.		
b	15/16 amps switch	5.00	Nos.		
c	3 pin 5/6 amps socket outlet	6.00	Nos.		
d	6 pin 15/16 amps socket outlet	5.00	Nos.		
11	Supplying and fixing following Modular GI/plastic base & cover plate on existing modular metal boxes/DLP plastic trunking etc. as required.				
a	1 or 2 Module	1.00	Nos.		
12	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	1.00	Nos.		
13	S & F following rating modular RJ-11 telephone jack (1M) complete with modular box i/c modular base & cover plate etc as reqd.	1.00	Nos.		
14	Fixing, Internet Box of size 75mm x 75mm x 40 mm including brass screw on surface / recessed as reqd.	4.00	Nos.		
15	Drawing of computer network cable/ PVC insulated flexible cooper/ Aluminium single core cable of size 1.5sqmm to 25 sqmm/ telephone cable upto 10 pair in existing pipe / casing and capping as reqd including numbering the wires at both the ends.	222.00	Mtr.		

S.N.	Description	Qty.	Unit	Rate (In Words & Figures)	Amount
16	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth metal enclosed plug top along with 20 amps ' C ' series SP, MCB, in the sheet steel enclosure, on surface or in recess, with chained metal cover for the soc	1.00	Nos.		
17	Supply, Installation, testing & commissioning of Ceiling fan of following 220 volts 50 Hz without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sqmm PVC insulated copper conductor single core cable etc as reqd.				
a	1200 mm sweep	1.00	Nos		

Total Rs.


 राघवेंद्र सिंह
 RAGHVENDRA SINGH
 अधिकारी अभियंता (वि०) E.E. (Elect.)
 सं. १०१०, भारतीय संस्थान, कानपुर
 Dept. W.D., I.I.T., Kanpur