

QUOTATION

Sub: Providing connection for 10 HP Motor alongwith other associated work at Geotechnical Engineering Field Laboratory.

S.N.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	3 x 4 Sq.mm	5.00	Mtr		
b	6 X 16 Sq.mm	60.00	Mtr		
2	Supply and drawing PVC insulated copper conductor (Flexible) 3 core round cable 1.5Sq.mm for connection of equipments / exhaust fan/AC & other work as reqd.	5.00	Mtr.		
3	Supplying and fixing of 32 mm dia X 2.00 metres long G.I. pipe (medium class) bracket for mounting of fluorescent / HPMV / HPSV street light fitting on pole including bending the pipe to the required shape, 2 nos 40 mm X 3 mm flat iron clamps with nuts, b	2.00	Nos.		
4	Supplying and fixing following rating, 240 volts, 'C' series, minature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc as reqd.				
a	Four Pole (40 Amp to 63 Amp)	1.00	Nos.		
5	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated shet cover in front including painting etc as reqd.				
a	200 mm X 250 mm X 60 mm deep	2.00	Nos.		
6	S & F metal enclosure suitable for DP/FP MCB/ on surface or recessed etc as reqd.	1.00	Nos.		
7	Supplying and fixing, 25 Watt LED street light luminaries with pressure die cast aluminium housing IP66 complete with all accessories complete	2.00	Nos.		
8	Supplying and fixing following piano type switch/socket on the existing switch box/cover including connections etc as reqd.				

S.N.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
a	5/6 amps switch	5.00	Nos.		
b	15/16 amps switch	3.00	Nos.		
c	5 pin 5/6 amps socket outlet	5.00	Nos.		
d	6 pin 15/16 amps socket outlet	3.00	Nos.		
9	Supply fixing connecting & commissioning of 15 Amp. 3 pin Plug top as reqd.	2.00	Nos.		
10	Structure steel work riveted, bolted or welded in built up sections, truses and framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	20.00	Kg.		

TOTAL Rs.


 राघवेंद्र सिंह
 RAGHVENDRA SINGH
 कनिष्ठ अभियंता (मि) E.E. (Electrical)
 सं. १०१०, माधुसूदन सराफ, बान
 W.D., I.I.T., Keppur