


QUOTATION

Name of work - Providing and Making two new plug points and earthing in advanced combustion and acoustics Lab and ACAL- Lab (Room No. 101 old SAC) and other associated works.

S. No	Description of Items	Qty	Unit	Rate	Amount
1	Supplying, installation DLP mini- trunking 32mm x 20 mm and accessories white-system with independent cover- without central partion etc. as reqd.				
a)	Mini- trunking	10.00	Mtr.		
b)	End cap left or right	2.00	Nos.		
2	Earthing with G.I earth pipe 4.5 mtr long, 40 mm dia including accessories, and providing masonary enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.	2.00	Set		
3	Providing & fixing GI earth strip of size 25mm x 5mm in ground / surface / existing pipe as per specification.	10.00	Mtr		
4	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
a)	3 x 1.5 Sq.mm..	15.00	Mtr.		
b)	2 x 6 Sq.mm..	5.00	Mtr.		
5	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
a)	6 module	1.00	Nos.		
6	S/F following modular base & cover plate on existing modular metal boxes etc. as reqd.				
a)	6 module	1.00	Nos.		
7	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
a)	5/6 Amp switch	2.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate	Amount
b)	3 Pin 5/6 Amp. socket outlet	2.00	Nos.		
8	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required				
a)	180 mm X 100 mm X 60 mm deep	1.00	Nos.		

Total Rs. _____


 राघवेंद्र सिंह
 RAGHVENDRA SINGH
 अभियंता (विद्युत) (विद्युत) (Elect)
 पेशवा विद्यापीठ, राणपूर, राणपूर
 P. E. D., I. T., Ranpur