


QUOTATION

Name of Work: Shifting of power cables from under construction area of PEB at Media Centre.

S. N.	Description of Items	Qty	Unit	Rate	Amount
				(In words & figures)	
1	Supplying & Laying of one no. PVC insulated & PVC sheathed aluminium conductor steel armoured cable of size 2 x 6 sqmm 1.1kV grade as reqd.				
a	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	30.00	Mtr.		
2	Supplying & Laying of one no. PVC insulated & PVC sheathed aluminium conductor steel armoured cable of size 3-1/2x50 sqmm 1.1kV grade .				
a	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	40.00	Mtr.		
3	Lifting & removing cable of following sizes from trenches or clamped on surface, making rol depositing the same in the store I/c cartage etc as reqd.				
a	Up to 35sqmm	25.00	Mtr.		
b	above 35sqmm and Up to 95 sq.mm.	30.00	Mtr.		
4	Laying of one no. PVC insulated, PVC sheathed/XLPE power cable of 1.1kV grade of size Upto 35 sq. mm				
a	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	20.00	Mtr.		
5	Laying of one no. PVC insulated, PVC sheathed/XLPE power cable of 1.1kV grade of size Above 35 sq. mm and upto 95 sq. mm.				
a	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	20.00	Mtr.		
6	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a	2x16 sqmm	2.00	Nos.		

S. N.	Description of Items	Qty	Unit	Rate (In words & figures)	Amount
b	3-1/2x 50 sqmm		2.00 Nos.		
7	Locating fault in the cable lines with megger etc. and rectifying moving & restoring supply the same & making good the damages etc as reqd.		2.00 Nos.		
8	Digging cable trench, lifting bricks & cable for locating fault. Refilling the trench, remaining & making good the same as reqd.	150.00	Mtr.		
	Total Rs.				


 राघवेंद्र सिंह
 RAGHVENDRA SINGH
 अधीनस्थ अधिकारी (सी) E.E. (Elect.)
 संचालक, जलविद्युत विभाग, काठमाडौं
 I.W.D., I.E.T., Kathmandu
