


QUOTATION

Name of Work:- Repairing and Maintenance of solar water heating system of R A Tower and Hall-12 and other associated works.

S.N.	Description of Items	Qty	Unit	Rate (in words & figures)	Amount
1	Replacement of damaged pipe line by providing and fixing of G.I. "C" class pipe i/c required fittings etc as required complete as per following specification and approved make. (Make_Jindal,Tata,QST or approved).				
a)	25 mm.	6.00	Mtrs.		
2	Providing & fixing 50 mm thick more than 48 Kg/cu Mtr glass wool insulation wrapped with wire mesh etc as required complete on 20/25/32 size hot water pipe line.	6.00	Mtrs.		
3	Providing & fixing 26 swg thick aluminium sheet cladding with screw make Hindalco or its equivalent approved make etc as required complete.	29.00	Mtrs.		
4	Supply and fixing electrical back-up 3 Kw with pocket ISI marked including heating element, & with capillary tube thermostate along with S.S. Enclosure fixed on element socket suitable for protection from water etc as reqd.	20.00	Nos.		
5	Dismantalling and refixing of existing GI/MS pipe line up to 32 mm dia complete as required.	75.00	Mtrs.		
6	Supply and drawing PVC insulated 3 core round cable of 2.5 Sq.mm size for connection of equipments / exhaust fan & other work as reqd.	50.00	Mtrs		
7	Locating and removing foul in Solar water line / system including replacement of CPVC, elbow, coupler, end cap etc. and removing air lock, cleaning choked lineetc as required complete.	150.00	Job.		

Total Rs.


राघवेंद्र सिंह
RAGHENDRA SINGH
अभिज्ञान इंजीनियरिंग (E.E. (Elect.))
राजिंदर नगर, लखनऊ, उत्तर प्रदेश
I.W.E., I. I. T., Kanpur