

INDIAN INSTITUTE OF TECHNOLOGY KANPUR

Tender Notice No. 17/IWD/ED/72

SCHEDULE OF QUANTITY

Name of work: Modification & renovation of electrical installation in SL-206.

Name of the Contractor					
S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.				
a	Group 'C'	9.00	Nos.		
2	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
a	Group 'C'	13.00	Nos.		
3	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	3 X 1.5 Sq.mm	40.00	Mtr		
b	3 X 2.5 Sq.mm	250.00	Mtr		
c	3 x 4 Sq.mm	50.00	Mtr		
d	3 x 6 sq. mm	50.00	Mtr		
e	3 x 10 Sqmm	10.00	Mtr.		
f	6 x 16 Sqmm	10.00	Mtr.		
4	Supplying and drawing following pair 0.5 Sq.mm FR PVC insulated copper conductor, unarmoured telephone cable in the existing surface/recessed steel/PVC conduit as reqd.				
a	2 Pair	50.00	Mtr		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
5	Supplying and fixing of following sizes of steel conduit along with accessories in surface/recess including painting in case of surface conduit, or cutting the wall and making good the same in case of recessed conduit as reqd.				
a	20 mm	10.00	Mtr		
b	25 mm	10.00	Mtr		
6	Supplying and fixing following of size/modules, GI box along with modular base & cover plate for modular switches in recess etc as reqd.				
a	12 module (200mm x 150mm)	2.00	Nos.		
7	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
a	12 Way, double door	1.00	Nos.		
8	Supplying and fixing following way prewired vertical type TP&N MCB distribution board of steel sheet for 415 volts on surface/ recess complete with loose wire box of sheet steel, dust protected, duly powder painted, inclusive of 200 amps tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCB's, terminal connectors for all incoming and outgoing circuits, duly prewired with adequate size of FR PVC insulated copper conductor upto the terminal connector/ neutral link, earthing etc as required (But without MCB/ RCCB/ Isolator).				
a	12 way (4 + 36) Double door	1.00	Nos.		
9	S & F following rating and pole, 240 volts 'C' curve 10 kA, lexic MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd.				
a	Single Pole (5 Amp to 32 Amp)	40.00	Nos.		
b	Double Pole (40 Amp to 63 Amp)	2.00	Nos.		
c	Tripple Pole (5 Amp to 32 Amp)	3.00	Nos.		
d	Tripple pole & Neutral (5 Amp to 32 Amp)	3.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
e	Tripple pole & Neutral (40 Amp to 63 Amp)	1.00	Nos.		
10	Supplying and fixing 20 amps, 240 volts, SPN industrial type, socket outlet, with 2 pole and earth metal enclosed plug top along with 20 amps ' C ' series SP, MCB, in the sheet steel enclosure, on surface or in recess, with chained metal cover for the soc	3.00	Nos.		
11	Supplying, installation DLP mini- trunking 32mm x 20mm and accessories white-system with independent cover-without central partion etc. as reqd.	30.00	Mtr.		
12	Providing and fixing DLP plastic trunking of size 105 mm x 50 mm without cover on surface as reqd.	50.00	Mtr.		
13	Providing and fixing 85 mm width flexible cover of DLP plastic trunking. (size 105 mm x 50 mm.)	48.00	Mtr.		
14	Supply and fixing of following items for plastic trunking accessories suitable for size 105 mm x 50 mm.				
a	End cap	10.00	Nos.		
b	Internal angle.	10.00	Nos.		
c	External angle	3.00	Nos.		
d	Flat Junction	1.00	Nos.		
e	Changeable flat angle	4.00	Nos.		
f	Separation partitions	30.00	Mtr.		
g	cover joint	10.00	Nos.		
h	Base joint	50.00	Nos.		
15	Supplying and fixing following modular switch/socket on the existing modular plate & switch box/ DLP plastic trunking including connections but excluding modular plate etc as reqd.				
a	5/6 amps switch	65.00	Nos.		
b	15/16 amps switch	58.00	Nos.		
c	3 pin 5/6 amps socket outlet	58.00	Nos.		
d	6 pin 15/16 amps socket outlet	58.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
e	Blanking Plate	5.00	Nos.		
16	Supplying and fixing following Modular GI/plastic base & cover plate on existing modular metal boxes/DLP plastic trunking etc. as required.				
a	1 or 2 Module	2.00	Nos.		
b	3 Module	5.00	Nos.		
c	6 Module	58.00	Nos.		
17	Supplying and fixing stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required.	8.00	Nos.		
18	S & F following rating moduler RJ-11 telephone jack (1M) complete with moduler base & cover plate etc as reqd.	2.00	Nos.		
19	Supply, Installation, testing & commissioning of Ceiling fan of following 220 volts 50 Hz without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sqmm PVC insulated copper conductor single core cable etc as reqd(Havells/Orient/ Bajaj make)				
a	1200 mm	8.00	Nos.		
20	S/F, connecting, testing and commissioning 34/35/36 watt LED recess mounted luminaires with diffuser suitable for 600 mm X 600 mm moduler POP/Gypsem ceiling etc.as reqd.	14.00	Nos.		
21	S/F, copper cable socket suitable for following size of conductor.				
a	6 Sqmm	6.00	Nos.		
b	10 Sqmm	6.00	Nos.		
c	16 Sqmm	12.00	Nos.		
22	Drawing of computer network cable in existing pipe / casing and capping as reqd including numbering the wires at both the ends.	400.00	Mtr.		
23	Fixing, Internet Box of size 75mm x 75mm x 40 mm including brass screw on surface / recessed as reqd.	15.00	Nos.		
24	S & F metal enclosure suitable for DP/FP MCB/ on surface or recessed etc as reqd.	3.00	Nos.		

S. No	Description of Items	Qty	Unit	Rate in Figures in Rupees	Amount
25	Extra for cutting and drilling hole & panting of down rod of G.I pipe,15 mm dia for ceiling fan etc as required.	8.00	Job		
26	Supplying & fixing 15 mm dia GI pipe for down rod for fixing of ceiling fans etc as reqd.	9.00	Mtr.		
27	S & F of following size of steel flexible pipe alongwith the accessories on surface etc as required.				
a	20 mm	10.00	Mtr.		
b	25 mm	5.00	Mtr.		
28	Dismantling the old conduit pipe/wood batten of all sizes from surface/recessed & making good the damages I/c filling the holes of the surface etc as reqd.	50.00	Mtr.		
29	Dismantling damaged DB/TPN Switches/ loose wire boxes/ M.S. boxes alongwith all accessories and depositing the same in the store as reqd.	15.00	Nos.		
30	Dismantling of ceiling fan / rally fan / all type fitting without regulator I/c depositing in store etc as reqd.	13.00	Nos.		
31	Dismantling, disconnecting 1x 1.5 / 2.5/ 4.0 / 6.0/ 10.0 sqmm wire from existing conduit pipe/batten/casing & capping and making role and depositing in store as reqd.	250.00	Mtr.		
	Total Rs.				