


## QUOTATION

Name of work:- Servicing of 2x500KVA DG set (NSM Data Centre) installed at Substation No. 11, feeding power backup to NSM data centre, Computer centre.

| S.N | Description of item  | Qty   | Unit | Rate                 | Amount |
|-----|--|-------|------|----------------------|--------|
|     |  |       |      | (In words & Figures) |        |
| 1   | Servicing& testing of 2x500KVA DG set of NSM Data Centre, complete by replacing following items as directed by Engineer In-charge. |       |      |                      |        |
| a   | Flex. Element with O ring  | 4.00  | each |                      |        |
| b   | Filter INSRT with O ring   | 4.00  | each |                      |        |
| c   | LUB Oil Filter 234   | 2.00  | each |                      |        |
| d   | Greaves Lub Oil 50 L CI-4  | 2.00  | each |                      |        |
| e   | Gasket - Rocker cover  | 24.00 | each |                      |        |
| f   | Radiator Pre-Mix Greaves Kool 10 LIT   | 4.00  | each |                      |        |
| g   | Packing and forwarding   | 1.00  | each |                      |        |

TOTAL Rs.

  
राघवेन्द्र सिंह  
RAGHENDRA SINGH  
अधिकाारी अधिवाना (दि. ००) E. E. (Elect.)  
सं. नि. वि. ०, मा. ०. ०. ० सं. वि. ०, का. न. न. न.  
I.W.D., I.I.T., Kanpur