

QUOTATION

Name of work :- Modification/Renovation of Electrical Installation of vacate house no-627, Type-IV at IIT Kanpur.


Sl. No.	Description of item	Qty.	Unit	Rate	Amount
(In words & Figures)					
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.				
1.1	Group B	7.00	Point		
2	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit/ PVC trunking as required.				
2.1	1 x 1.5 sq. mm	90.00	Mtr.		
2.2	3 x 1.5 sq. mm	80.00	Mtr.		
2.3	3 x 4 sq. mm	95.00	Mtr.		
3	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
3.1	5/6 amp switch	30.00	Each		
3.2	2 way 5/6 amp switch	2.00	Each		
3.3	3 pin 5/6 amp socket outlet	10.00	Each		
3.4	15/16 amp switch	6.00	Each		
3.5	6 pin 15/16 amp socket outlet	6.00	Each		
3.6	Telephone socket / jack outlet	2.00	Each		

Sl. No.	Description of item	Qty.	Unit	Rate	Amount
				(In words & Figures)	
4	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box/ wooden block including connections etc. as required.	20.00	Each		
5	Supplying and fixing brass batten/ angle holder including connection etc. as required.	10.00	Each		
6	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	1.00	Each		
7	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)				
7.1	16 way, Double door	1.00	Each		
8	Supply, Installation, Testing and Commissioning of 1200 mm sweep, BEE 5 star rated, ceiling fan with Brush Less Direct Current (BLDC) Motor, class of insulation: B, 3 nos. blades, 30 cm long down rod, 2 nos. canopies, shackle kit, safety rope, copper winding, Power Factor not less than 0.9, Service Value (CMM/W) minimum 6.85, Air delivery minimum 215 CMM, 350 RPM (tolerance as per IS : 374-2019), THD less than 10%, remote or electronic regulator unit for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise=75 degree C (max.), insulation resistance more than 2 mega ohm, suitable for 230 V, 50 Hz, single phase AC Supply, earthing etc. complete as required.	5.00	Each		
9	Supplying and fixing 5 amps to 32 amps rating, 240/415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
9.1	Single pole	16.00	Each		

Sl. No.	Description of item	Qty.	Unit	Rate	Amount
				(In words & Figures)	
10	Supplying and fixing following rating, double pole, (single phase and neutral), 240 V, residual current circuit breaker (RCCB), having a sensitivity current 300 mA in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
10.1	63 Amp	1.00	Each		
11	Supplying and fixing following piano type switch/ socket on the existing switch box/ cover including connections etc. as required.				
11.1	Fan Regulator socket type	4.00	Each		
12	Providing and fixing PVC casing and capping in place of defective and damaged wood batten including dismantling of batten and wire complete as required.				
12.1	20 X 12 mm	45.00	Mtr.		
12.2	25 X 16 mm	40.00	Mtr.		
12.3	32 X 16 mm	15.00	Mtr.		
13	Supplying and fixing wooden board of following sizes on surface/recessed with suitable size of phenolic laminated sheet cover etc. complete as required.				
13.1	100 mm X 100 mm	20.00	Each		
13.2	175 mm X 100 mm	8.00	Each		
13.3	200 mm X 150 mm	3.00	Each		
13.4	200 mm X 250 mm	2.00	Each		
14	Dismantling damaged DB/TPN Switches/ loose wire boxes along with all accessories and depositing the same in the store as req	1.00	Each		

Sl. No.	Description of item	Qty.	Unit	Rate	Amount
(In words & Figures)					
15	Supplying and fixing 3 mm thick phenolic laminated sheet on existing board with brass screw and cup washer etc. complete as required.	800.00	Sq.cm		
16	Supplying, fixing, testing & commissioning of 12W LED. Slim surface mounted round LED panel al. die cast body with premium diffuser to ensure glare free etc. complete as required.	2.00	Nos.		
17	Supplying, fixing, connecting, commissioning and testing of the following luminaries light fixtures complete with all accessories and without lamp as required complete.				
17.1	Drum light fitting suitable for 60W GLS lamp	2.00	Each		
17.2	Wall bracket fitting suitable for 60W GLS lamp	5.00	Each		
17.3	Bulk head fitting suitable for 60W GLS lamp	5.00	Each		
18	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	6.00	Each		
19	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	20.00	Each		
20	Supplying and drawing telephone cable of 2 pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.	10.00	Mtr.		

Total Rs.


 RAGHVENDRA SINGH
 अधिरापी अभियंता (वि०) E.E. (Elect.)
 सं०नि०वि०, मा०रो० संस्थान, कानपुर
 I.W.D., I.I.T., Kanpur
