


QUOTATION

Name of work: Replacement of defective telephone DP Box Near Type- 1B /1 and Type-2 area .

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & figures)	
1	Providing brick work (in width 225 mm or more) with F.P.S. bricks of class designation 7.5 in cement mortar 1:4 (1 cement : 4 coarse sand) at all levels.	8.00	Cum		
2	Providing 15mm thick cement plaster of mix 1:4 (1 cement : 4 fine sand) at all levels.	15.00	sqm		
3	Fixing of telephone DP/network rack (HUB) on wall floor with suitable brick foundation on bolts and nut etc. as reqd.	6.00	Nos.		
4	Digging cable trench, lifting brick & cable for locating fault and relaying the cable i/c/ refilling the trench, extra sand if required shall be i/c in the item of following size. as required.				
a)	not exceeding 35 sq.mm..	180.00	Mtr		

Total Rs


राघवेंद्र सिंह
RAGHVENDRA SINGH
अधिकाधी अधिकाधी (वि०) E.E. (Elect.)
संवि०वि०, मा०पी० संस्थान, कानपुर
L.W.D., I.I.T., Kanpur
