

## QUOTATION

**Name of Work:-** Repairing & Maintenance of Solar water heating system installed at A, B, C Blocks of Hall-12 and other associated work in order to make it operational.


S.	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
1	Dismantling, cleaning, descaling, overhauling of collectors & hot water pipe line of installed solar water heating system with proper chemical / liquid soap etc. and neutralizing the same complete as required.	60.00	Nos.		
2	Painting two coat of solar hot water complete system including collector stand, hot water storage and makeup tank stands, pipe sports after cleaning the surface with sand paper / cloth etc as reqd..	60.00	Nos.		
3	Dismantling and refixing solar Panel after repairing leakage in Solar panel pipe and removing air lock, cleaning choked line etc as required complete.	1.00	Nos.		
4	Supply fixing connecting & commissioning of 2/3 kW heating element in Solar water tank / geyser. as required complete	4.00	Nos.		
5	Supply fixing connecting & commissioning of thermostat suitable for geyser. as required complete	4.00	Nos.		
6	Supply fixing connecting & commissioning of 15/16Amp. rating 3 pin Plug top Anchor makeas reqd complete.	4.00	Nos.		
7	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.				
7.1	25 mm dia nominal bore	12.00	Mtr.		
8	Providing and fixing solar glass for flat plate collector of capacity 100 LPD complete as required.	1.00	Nos.		

S. Description of Items	Qty	Unit	Rate	Amount
			(In words & Figures)	

7 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.

30.00 Kg.

Total Rs.

  
 RAGHVEN  
 अचिरापी अभियंता  
 सं. नि. वि. सं. प्र.  
 I.W.D., I.I.I., Kanpur

SINGH  
 E.E. (Elect.)  
 ज्ञान, कानपुर  
