

INDIAN INSTITUTE OF TECHNOLOGY KANPUR
INSTITUTE WORKS DEPARTMENT
ELECTRICAL & AIR-CONDITIONING DIVISION

No. 35 /AC/EE/2021/ 375

Dated 03-02-2021

QUOTATION NOTICE

M/s

Sealed quotations are invited from the empanelled contractors by the undersigned on behalf of the Director, IIT Kanpur for "**Replacement of damage part of defective power cable with associated works of F & G Block at Girls Hostel_1.**" As per enclosed Bill of Quantity/ overleaf, so as to reach in this office on or before 12-02-2021 upto 3.00 PM and the quotation will be opened on the same day at 3.30PM in the presence of quotationers or their representative who want to be present.

The terms and conditions of the quotation are as under:

1. The quotations should be submitted in a properly sealed envelop, addressed to the undersigned. The enquiry nos. and date should invariably quoted on the top of the envelop.
2. The time allowed for carrying out the above noted work is 28(Twenty Eight) Days.
3. The rates quoted should be exclusive of GST, no other tax is payable except GST. GST shall be applicable as per Govt. norms..
4. Security @ 7.5% shall be deducted from the bills which shall be released on successful completion of defect liability period of six months.
5. The estimated cost of quotation is **Rs.94731/-**. The required earnest money of **Rs. 1895/-** is to be submitted in the form of FDR pledged in favour of the Director, IIT Kanpur alongwith the quotation. The earnest money of the unsuccessful quotationers will be returned within one month's time.
6. The quotations shall remain valid for 90 days from the date of opening.
7. Income tax will be recovered as per notification of Government from the bill and the amount so recovered will be deposited in the State Bank of India at the credit of the firm.
8. The earnest money/Security deposit will be regulated as per the norms of C.P.W.D..
9. The Institute reserves the right of accepting or rejecting any quotations without assigning any reason thereof.
10. The material should be used as per approved list of make.

QUOTATION

Sub: Replacement of damage part of defective power cable with associated works of F & G Block at Girls Hostel_1

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
1	Supply, laying, testing and commissioning of one no. PVC insulated & PVC sheathed aluminum conductor steel armoured cable of following sizes 1.1kV grade A in following manners as per specifications reqd.				
(A)	In ground i/c excavation sand cushioning protective covering, refilling of earth etc.				
a)	3½ x 120 sq.mm.	40.00	Mtr.		
(B)	Additional cable in ground i/c excavation sand cushioning protective covering, refilling of earth etc.				
a)	3½ x 120 sq.mm.	40.00	Mtr.		
(C)	On surface				
a)	3½ x 120 sq.mm.	5.00	Mtr.		
(D)	On existing pipe				
a)	3½ x 120 sq.mm.	10.00	Mtr.		
(E)	On existing open duct.				
a)	3½ x 120 sq.mm.	15.00	Mtr.		
2	Locating fault in the cable lines with meager etc. and rectifying removing & restoring supply the same & making good the damages etc (temporary) as reqd.	2.00	Nos.		

S.N.	Description	Qty.	Unit	Rate (Rs.) Words & Fig.	Amount
3	Digging cable trench, lifting bricks, cable and relaying the cable after locating fault including refilling trench & ramming etc. Complete as required..	60.00	Mtr.		
4	Providing 1/3 phase temporary service connection from supply source to desired place up to the lead/ cable 35 sq. mm. of 50 mtr. and disconnecting the same including to & fro cartage. (extension board and cable will be supplied by the dept.)	2.00	Nos.		
5	Dismantling, lifting & removing cable of any size from trench/ clamps on surface, making roll depositing the same in the store l/c cartage etc as reqd.	50.00	Mtr.		
6	Supplying and making end termination with brass compression gland, aluminum lugs for following size of PVC insulated & PVC sheathed / XLPE aluminum cable of 1.1kV grade as reqd.				
a)	3½ X 120 sq. mm (45mm)	2.00	Nos.		
7	Supply and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a)	3½ X 120 sq. mm	2.00	Nos.		
8	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep) and re-filling etc as required				
a)	50 mm dia	3.00	Mtr.		
b)	100 mm dia	3.00	Mtr.		
Total Rs.					