

QUOTATION

Name of work:-Replacement of old & damaged faulty telephone cable & wire in houses No.215 Type-2 & 456 Type-IV in the campus.

S.No.	Description	Qty.	Unit	Rate	Amount
				(in words & figures)	
1	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required				
a)	50 mm dia	5.00	Mtr.		
2	Supplying and drawing telephone cable of 2 pair 0.5 mm dia FRLS PVC insulated annealed copper conductor, unarmored telephone cable in the existing surface/ recessed steel/ PVC conduit as required.	60.00	Mtr.		
3	Supplying and laying following pairs jelly filled armoured telephone cable of 5 pair PVC insulated and PVC sheathed tinned copper conductor.				
a)	In ground I/c excavation, sand cushioning.	60.00	Mtr.		
b)	In pipe	4.50	Mtr.		
c)	In open duct	5.00	Mtr.		
d)	On surface with MS clamp	2.00	Mtr.		
4	Fixing Telephone DP upto 400 pairs on wall/ floor with required nut bolts/fixing arrangements as required complete.	2.00	Nos.		
5	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	25 x 16 mm	20.33	Mtr.		
6	Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				

S.No.	Description	Qty.	Unit	Rate (in words & figures)	Amount
-------	-------------	------	------	------------------------------	--------

a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	20.00	Mtr.		
b)	In pipe	20.00	Mtr.		
c)	On surface with MS clamp	5.00	Mtr.		
d)	In open duct	12.00	Mtr.		

Total Rs

R Singh
 PACIFIC TRADING
 1/23

Devi