

QUOTATION


Name work : Shifting of One Feeder pillar of Taxi stand near Gate no. 2 IIT Kanpur.

S.No	Description	Qty	Unit	Rate (In words & figures)	Amount
1	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required	2.00	Nos.		
2	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required	10.00	Mtr.		
3	Providing and fixing 6 SWG dia. GI wire on surface or in recess for loop earthing as required.	30.00	Mtr.		
4	Supplying and making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1kV grade as reqd.				
a	2x16 sqmm, 2x10 sqmm, 2x6 sqmm	6.00	Set		
5	Providing brick work (in width 225 mm or more) with F.P.S. bricks of class designation 7.5 in cement mortar 1:4 (1 cement : 4 coarse sand) at all levels.	3.00	Cum		
6	Providing 15mm thick cement plaster of mix 1:4 (1 cement : 4 fine sand) at all levels.	6.00	Sqm		
7	Supplying & Laying of one no. XLPE cable aluminium conductor steel armoured cable of size 2x6sqmm, grade 1.1kV in following manners.				
a	In Ground I/c excavation, sand cushioning protective covering, refilling of earth as reqd.	30.00	Mtr.		
b	In existing open duct	20.00	Mtr.		

S.No	Description	Qty	Unit	Rate (In words & figures)	Amount
8	Supplying & Laying of one no. XLPE cable aluminium conductor steel armoured cable of size 2x10sqmm, grade 1.1kV in following manners.				
a	In Ground I/c excavation, sand cushioning protective covering, refilling of earth as reqd.	30.00	Mtr.		
b	In existing open duct	20.00	Mtr.		
9	Digging cable trench for taking out cable and refilling , watering ,ramming the sameafter taking out cable as reqd complete.	60.00	Mtr.		
10	Dismantling and refixing brass compression type gland up to 400 sq. mm. cable	12.00	Nos.		
11	Dismantalling, Disconnecting,of existing and refixing , reinstallation of street light, feeder pillar Instruction by Engineer In-Charge by labours, repairing , finishing etc.complete as required.	1.00	Nos.		

Total Rs.

=====
=====


 राघवेंद्र सिंह
 Raghvendra Singh
 इलेक्ट्रिकल अभियन्ता (वि०)/E.E. (Elect.)
 एन.ए.पी.डी. काठ प्रौद्योगिकी संस्थान, कानपुर
 I.W. 100, I.E.T. Kanpur
