

QUOTATION

Name of Work: Replacement of defective & damaged street lights / MCCB as per enclosed complaint at Nursary, V.H. Ext. Block C with other Allied work at IIT Kanpur.

S. No	Description of Items	Qty	Unit	Rate (Rs.) Words & Fig.	Amount
1	Supplying,fixing,testing commissioning of energy saving, environmental friendly,long life,exclusive innovative die cast aluminium IP 65 with high poer LEDs as light source. following LED flood light make Havells, having symmetric optics or its equivalent, on the existing pole complete as required.				
1.1	70-80W LED Flood light (Ca. No.- FLARENEOCA 80W LED 757PSYMLTG)	5.00	Nos.		
2	Dismantling cross arm / street light brakcet/street light fitting from any size of pole complete as required and depositing in sectional store.	4.00	Nos.		
3	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	1.00	Set		
4	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ recessed conduit/ submain wiring/ cable as required.	10.59	Mtr.		
5	Supply and drawing PVC insulated 1.5 Sq.mm 3 core round cable of following size for connection of equipments / exhaust fan & other work as reqd.	7.00	Mtr.		

