

QUOTATION

Name of work:-Repairing/replacement old faulty cable of 2 x 6 sq mm XLPE armoured cable of DG Supply at SS-5 incoming from DTW-6 in the campus.

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
1	Supplying and making indoor end termination with brass compression gland, aluminum lugs for following size of PVC insulated & PVC sheathed/XLPE aluminum cable of 1.1kV grade as reqd.				
a)	2x6 sq.mm.	2.00	Nos.		
2	Supplying & Laying of one no. XLPE sheathed aluminum conductor steel armoured power cable of size 2 x 6 sq.mm. 1.1kV grade in following manners.				
a)	direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	80.00	Mtr.		
b)	In pipe	2.00	Mtr.		
c)	In open duct	1.00	Mtr.		
d)	On surface with MS clamp	12.00	Mtr.		
3	Digging cable trench, lifting brick & cable for locating fault and relaying the cable i/c refilling the trench, extra sand if required shall be i/c in the item of following size. as required.	9.77	Mtr.		
Total Rs.					_____


RAGHENDRA SINGH
संस्थापक (E.E.) E.E. (Elect)
I.W.D., M.T., Kanpur
