

QUOTATION

Name of work: Replacement of damaged LAN wire of House No 420 Type-4, 294 Type-II, W-9 SBRA, 602 C Block FA, 230 Type-1B in the campus -1B in the campus as per complaints on pingala.


S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	
1	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	6.00	Nos.		
2	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	420.00	Mtr.		
3	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
a)	20 x 12 mm	20.00	Mtr.		
b)	25 x 16 mm	25.00	Mtr.		
c)	32x 16 mm	20.00	Mtr.		
4	Supply and laying of HDPE pipe ISI mark of 25 mm (8Kg / cm ²) size inner dia, 2mm thick I/c cartage loading & unloading etc. as reqd.				
a)	Direct in ground I/c excavation, sand cushioning, protective covering and refilling the trench etc. as reqd.	150.00	Mtr.		

S.No.	Description	Qty.	Unit	Rate	Amount
-------	-------------	------	------	------	--------

(In words & Figures)

b)	In pipe	50.00	Mtr.		
c)	In open duct	5.00	Mtr.		
d)	On surface with MS clamp	10.00	Mtr.		

Total Rs


अधिराजी अभियन्ता (वि.) / E.E. (Elect.)
संविनिति, मां प्रौ संस्थान, कानपुर
I.W.D., I.I.T. Kanpur
Devi