

## QUOTATION

Sub:- **Providing power points for Fan coil unit for air conditioning in NL-I-311, 311A, 311B, and internet points for wifi in Nuclear 1st floor-201 & corridor.**

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In words & Figures)					
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	130.00	Metre		
2	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	88.00	Meter		
3	Supply and fixing of following accessories suitable for 32 mm x 20 mm size plastic trunking white system.				
a	End cap	4.00	Nos.		
b	internal / external angle	8.00	Nos.		
c	changeable flat angle	9.00	Nos.		
d	flat junction	3.00	Nos.		
4	S & F following size of steel flexible pipe alongwith the accessories on surface etc as required				
a	20 mm	15.00	Meter		

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
--------	-------------	-----	------	------	--------

(In words & Figures)

b 25 mm 1.00 Meter

5 Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.

a 5/6 A switch 17.00 No.

b 3 pin 5/6 A socket outlet 17.00 No.

6 Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.

a for 2 Module 2.00 No.

b 3 Module 16.00 No.

7 Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.

a 1 or 2 Module 2.00 Nos.

b 3 Module 16.00 Nos.

8 Supplying and fixing following rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.

a Single pole 5 A to 32 A 5.00 Nos.

SL No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
--------	-------------	-----	------	------	--------

(In words & Figures)

9 Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)

275.00 Meter

10 Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. ( box and cover plate will be supplied by dept.)

7.00 Nos.

**Total Rs.**

अधिराशी अभियन्ता (विद्युत) / E.E. (Elect.)  
 मॉडर्नाइजेशन, माओ प्रौद्योगिकी संस्थान, कानपुर  
 I.W.D., I.I.T. Kanpur

*(Signature)*