


## QUOTATION

**Name of work :-** Overhauling of ceiling fans, exhaust fan installed at Hall-12 E-202, A-110, C-6 washroom, F & D Drying area and other associated work.

S.No.	Description of work	Qty.	Unit	Rate (In words & figures)	Amount
1	Overhauling of fan of any size including dismantling and refixing of fan, bearings, checking, cleaning the all parts and supplying & replacement of rubber real, rubber rings, nut bolts, hanger clamps, bearing plates, cotter/ split pin, varnishing if reqd etc, reassembling testing and commissioning of fan as required complete.	36.00	Nos.		
2	Overhauling of exhaust fan of any size including dismantling of all parts and cleaning the fan with kerosene oil / petrol removing ball bearing/ bush and refixing after greasing/ oiling including testing and commissioning as required complete. (spares will be supplied by the Dept.)	5.00	Nos.		
3	Supplying and fixing 2.5 mfd capacitor suitable for ceiling fan.	16.00	Nos.		
4	Repairing of housing of bearing side /bush side /in fan body in ceiling fan /exhaust fan/ rally fan etc.	5.00	Nos.		
5	Dismantling & refixing of any size following fan from normal height.				
a)	exhaust fan	5.00	Nos.		
6	Cartage of Ceiling fans and regulator / exhaust fan From store to site as reqd.	5.00	Nos.		

**Total**

  
श्री श्री लोचन (पि)/E.E.(E-202)  
सहायक, आर प्रो रक्षक, कानपुर  
I.W.D., I.I.T. Kanpur  
