

QUOTATION

Sub Repairing/replacement of defective electrical items in Old LH L2, FB 335,Imagineering Lab,SL 205 and different labs and offices in academic area on complaint basis.


S.N	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
a	3 x 1.5 sq. mm	8.00	Metre		
b	3 x 2.5 sq. mm	29.00	Metre		
c	2 x 25 sq.mm.	30.00	Meter		
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
a	5/6 A switch	17.00	No.		
b	15/16 A switch	17.00	No.		
c	3 pin 5/6 A socket outlet	17.00	No.		
d	6 pin 15/16 A socket outlet	17.00	No.		
3	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
a	12 Module (200mmX150mm)	1.00	No.		
4	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.				

S.N	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
a	lor 2 Module	2.00	No.		
b	6 Module	4.00	No.		
5	Supply fixing connecting & commissioning of following rating ISI marked 3 pin Plug top Anchor make as reqd complete.				
a	5 Amp	1.00	Nos.		
b	15 Amp	1.00	Nos.		
6	S&F, Copper tube / reducer/ lug terminals suitable for following size of conductor.				
a	25/35/50 Sq.mm.	8.00	Nos.		
7	Supply and drawing PVC insulated 3 core round copper conductor cable of following size for connection of equipment / exhaust fan etc as reqd.				
a	2.50 sq. mm	5.00	Meter		
8	Supply and fixing of 32 x 20 mm DLP mini- trunking white-system with independent cover etc. as required complete.	25.00	Meter		
9	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	400.00	Meter		

S.N	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
10	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	12.00	Nos.		
11	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	2.00	Nos.		
12	Dismantling, disconnecting old damaged unserviceable fl fitting/ exhaust fan/ ceiling fan/ bulkhead fitting with bracket etc. as reqd. and depositing in sectional store.	5.00	Nos.		
13	Supplying and fixing wood box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front etc as required.				
a	250 mm x 300 mm	1.00	Nos.		
14	Supplying and fixing following size/ modules, plastic box for modular switches in recess etc as required.				
a	1 or 2 Module	2.00	Nos.		
b	6 Module	2.00	Nos.		
c	12 Module	1.00	Nos.		
15	Supply and fixing of following LED light fixture with efficiency >100 lumen/ watt, P.F. >0.95, THD<10%, Electronic driver, LED lamp, reflector, diffusser, MS body/housing holder etc. complete with all fixing accessories and lamp as required complete.				

S.N	DESCRIPTION	QTY	UNIT	RATE (In words & Figures)	AMOUNT
a	1 X 20W Box type LED tube with fitting	4.00	Nos.		
b	36 watt recess mounting LED light fixture 600 x 600 mm	2.00	Nos.		
c	36 watt recess mounting LED light fixture 300 x 1200 mm	2.00	Nos.		
16	Supply, Installation testing and commissioning of following seep, copper wound, 900 RPM, 220 volt AC, 50 Hz exhaust fan in the existing opening etc as required complete.				
a	450 mm / 18" sweep	1.00	Nos.		
17	Supplying and fixing connecting and commissioning of AC 230/250 volts, 50 HZ, 250 mm sweep fresh air fan including providing nuts, bolts, mounting frame and other accessories etc. complete	1.00	Nos.		

Total Rs.


 एम.डी. प्रो. प्रो. (एच.ए.)/ए.ए. (एल.ए.)
 एम.डी. प्रो. प्रो. सहाय, कानपुर
 E.W.D., U.T. Kanpur
