


## QUOTATION

Sub: Preventive maintenance of electrical panels installed in various switch rooms of academic area.

S.No.	Description	Qty	Unit	Rate (In words & Figures)	Amount
1	Preventive maintenance of LT switch gear panel set consisting of different capacity ACB's, MCCB's SFU/FSU 1 $\phi$ / 3 $\phi$ 50Hz, as incomer/ out going, metering equipments control switches, CT, PT, indicating lamps etc. including cleaning and removal of minor defects, checking and cleaning of contacts with CTC, checking and tightening of connections etc.	30.00	Job		
2	Replacement of defective and damaged panel lock made of high carbon steel body brass movment duly nickel plated in exiting LT panel as required complete.	72.00	Each		
3	Replacement defective and damaged indicating light with LED indicator light of similar voltage level including dismantling of existing lamp as required complete.	15.00	Each		
4	Replacement of following defective and damaged HRC fuse link cylindrical type HF including dismantling of existing HRC fuse as required complete.				
a	32 Amp	10.00	Each		
b	63 Amp	5.00	Each		
<b>Total Rs.</b>					_____

  
RAGHVENDRA SINGH  
संस्थापक अभियंता (सि. ई. ई.) (Elect.)  
सं. लि. वि. भ. सं. ई. सं. थान, कानपुर  
I.W.D., L.I.T., Kanpur  
