

QUOTATION


Name of work: Providing LAN ports in the New lab old SAC Area (prefab building,C Block Ground Floor).

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Fixing of RJ-45 modular box with cover plate or I/o box for internet on surface/ recessed cutting the wall making good the same as required. (box and cover plate will be supplied by dept.)	20.00	Nos.		
2	Laying UTP cable enhanced cat 5/cat 6 cable in existing steel conduit pipe/GI pipe/ raceway / RCC pipe as reqd. the cost shall also include numbering of networking wire from room to rack as reqd. (wire will be supplied by dept)	400.00	Mtr.		
3	Providing and fixing DLP plastic trunking of size 105 mm x 50 mm without cover on surface as reqd.	40.00	Mtr.		
4	Providing and fixing 85 mm width flexible cover of DLP plastic trunking (size 105 mm x 50 mm.)	40.00	Mtr.		
a	Supply and fixing of following items for plastic trunking accessories suitable for size 105 mm x 50 mm.				
b	End cap	5.00	Nos.		
c	Internal angle.	4.00	Nos.		
d	External angle	4.00	Nos.		
e	Flat Junction	3.00	Nos.		
f	Changeable flat angle	3.00	Nos.		
g	Separation partitions	5.00	Mtr.		
h	cover joint	10.00	Nos.		
i	Base joint	20.00	Nos.		

S.No.	Description	Qty.	Unit	Rate	Amount
				(In words & Figures)	

5	Supplying, installation DLP mini-trunking 32mm x 20mm and accessories white-system with independent cover- without central partion etc. as reqd.				
a	Mini- trunking	30.00	Mtr.		
b	End cap left or right	5.00	Nos.		
c	Internal/ external angle	5.00	Nos.		
d	Flat angle	3.00	Nos.		
e	Flat junction	4.00	Nos.		

Total Rs


 राघवेंद्र सिंह
 RAGHVENDRA SINGH
 अध्यापक (वि. वि. ए. (सि. वि.))
 एम. वि. वि. (वि. वि. ए. (सि. वि.))
 (V.V.T., I.I.T., Kanpur)