


## QUOTATION

**Name of work :-** Repairing of underground service cable. from feeder pillar 25 to feeder pillar 25A at lane- 33 as per enclosed complaints at IIT Kanpur.

S.N.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
(In words & Figures)					
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size direct in ground including excavation and refilling the trench etc as required, but excluding sand cushioning and protective covering.				
1.1	Above 185 sq. mm and upto 400 sq. mm	115.00	Mtr.		
2	Digging trench for taking out cable upto 400 Sq.mm. and refilling , watering ,ramming the same after taking out cable as reqd complete.	120.00	Mtr.		
3	Lifting removing cable of following size from trench/clamps, making roll & depositing the same in store I/c cartage.				
3.1	above 185 upto 400 Sq.mm.	100.00	Mtr.		
4	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
4.1	3½ X 240 sq. Mm	1.00	Nos.		
5	Locating fault in the cable lines with meggar etc and rectifying removing & restoring the same and making good the damages etc as required.	1.00	Nos.		
6	Dismantling & refixing brass compression type cable gland 25 sq.mm to 400 sq.mm. cable.	2.00	Nos.		

Total Rs.

  
आचार्य (विद्युत) (विद्युत) ए.ए. (विद्युत)  
सहायक, पाठशाला सभ्यता, कानपुर  
(W.P., I.I.T., Kanpur)  
