


QUOTATION

Name of work:-Electrical Maintenance work at Kendriya Vidyalaya as per enclosed complaints in the campus.

S.No.	Description	Qty.	Unit	Rate (In words & Figures)	Amount
1	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MCB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A, tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) as required. (Note : Vertical type MCB TPDB is normally used where 3 phase outlets are required.)				
a)	4-way Cat no. 607750 Legrand or equivalent	1.00	Nos.		
2	S & F 40 amp to 63 amp rating 240 volts, 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd. (legrand or equivalent)				
a	Triple pole	4.00	Nos.		
b	Four Pole	2.00	Nos.		
3	Locating fault in the cable lines with meager etc. and rectifying removing & restoring supply the same & making good the damages etc as reqd.	1.00	Nos.		

Total Rs.


अधिकाधी अभियता (वि०) E.E. (वि०)
संनितवि०, भा०प्री० संस्थान, कानपुर
I.W.D., I.I.T., Kanpur
