


QUOTATION

Name of work : Replacement of damaged main switch (200A) of emergency stage lights & other electrical repairing in auditorium for upcoming convocation programme.

S.No	Description of Items	Qty	Unit	Rate (In words & Figures)	Amount
1	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.				
a	250 A,36KA,FPMCCB	1.00	Nos.		
2	Supplying, connecting and commissioning of following size aluminium bus bar including bending to suitable shape, making hole for nut-bolts, providing and fixing bus bar insulators, slivering, nut-bolts in existing panel/box for connections etc. as required complete.				
a	1x25x6mm	4.00	Mtr		
3	Fabrication, supplying & fixing of box of required size made out of 2mm thick CRCA sheet duly powder coated & openable from top-bottom or front required & fixing the same complete as required.	10.00	Kg		
4	Servicing, repairing, cleaning Testing and commissioning and Painting with two or more coats of existing LT Panel complete as instruction by Engineer In-charge etc. complete as required.	2.00	Nos.		

S.No	Description of Items	Qty	Unit	Rate	Amount
(In words & Figures)					
5	Overhauling of ceiling fan of any size including dismantling and refixing of fan, bearings, checking, cleaning the all parts and supplying & replacement of rubber real, rubber rings, nut bolts, hanger clamps, bearing plates, cotter/ split pin, varnishing if reqd etc, reassembling testing and commissioning of fan as required complete.	25.00	Nos.		
6	Supply of panel lock Inner of brass and outer is Ms-steel (heavy duty) made for in existing LT panel / feeder pillar in the place of damaged lock complete as directed by Engineer In-charge.	40.00	Nos.		
7	Disconnecting and Dismantalling damaged pole fuse box/ Changeover Switch/ MCCB/ Contactor /DB/KWH meter of any size from site and depositing in store I/c cartage etc. as reqd.	2.00	Nos		

Total Rs.



अधिसाक्षी अभियंता (वा०) E.E. (A.C.)
सं० नि० वि०, मा० प्रौ० संस्थान, कानपुर
I W.D. LLT Kanpur