

## QUOTATION

Name of work -:Electrical maintenance works at H No. 607, 233, 223, 203, 281 294, 2009 Type-II, A3 V F A, S.G -Centre MedTech Lab, V H PEB Yoga Centre, K3 Old SBRA, H No. M2, FA/A301, H No. 50A, FA/B104, FA/A-304 Type-4, FA-B303, R3 Media lab Asia, H No.2075 CFL, B-1 SBRA, 4008, 4075, H No. 458 Type-II etc. south side residences as per enclosed complaints.

S.No	Description	Qty	Unit	Rate	Amount
(In words & Figures)					
1	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
1.1	3 x 1.5 Sq.mm..	6.50	Mtr.		
1.2	3 x 4 Sq.mm..	33.00	Mtr.		
2	S & F following piano type switch /socket on existing switch box/cover I/c				
2.1	5/6 Amp switch	3.00	Nos.		
2.2	3 Pin 5/6 Amp. socket outlet	2.00	Nos.		
3	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
3.1	5/6 Amp switch	11.00	Nos.		
3.2	15/16 Amp. switch	4.00	Nos.		
3.3	3 Pin 5/6 Amp. socket outlet	2.00	Nos.		
3.4	6 Pin 15/16 Amp. socket outlet.	3.00	Nos.		
4	S & F following size/modules, GI box along with modular base and cover plate for modular switches in recess etc.as required.				
4.1	3 module	1.00	Nos.		

S.No	Description	Qty	Unit	Rate	Amount
				(In words & Figures)	
5	S/F following modular base & cover plate on existing modular metal boxes				
5.1	1 or 2 module	1.00	Nos.		
5.2	3 module	3.00	Nos.		
5.3	4 module	2.00	Nos.		
6	Supplying and fixing call bell/ buzzer suitable for D.C./A.C. single phase, 230 volts, complete as required.	1.00	Nos.		
7	S & F following rating double pole (single phase & neutral) 240 volts RCCB (ELCB), having sensivity current up to 300 mA in the existing MCB DB complete with connection,testing & commissioning etc as reqd.				
7.1	63 Amp	1.00	Nos.		
8	Supplying and fixing DP sheet steel enclosure on surface/ recess along with 25/32 A 240 V "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	1.00	Nos.		
9	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel / PVC conduit as reqd.				
9.1	3 x 10 Sq.mm..	3.00	Mtr.		
10	S & F 40 amp to 63 amp rating 240 volts 'C' curve 10 kA MCB of following pole in the existing MCB DB complete with connection, testing & commissioning etc as reqd. ( legrand or its equivalent as per approved make list)				
10.1	Double pole	1.00	Nos.		
11	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				

S.No	Description	Qty	Unit	Rate	Amount
				(In words & Figures)	
11.1	20 x 12 mm	9.50	Mtr.		
11.2	32x 16 mm	0.84	Mtr.		
12	Supply / fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make- Phillips its equivalent as per approved make list))				
12.1	LED bulb 5W to 10 W	1.00	Nos.		
12.2	LED tube light 18 / 20 Watt.	1.00	Nos.		
13	Dismantling and refixing of switch / socket /regulator I/c cleaning, connecting, commissioning etc as reqd.	7.00	Nos.		
14	Locating fault in wiring rectifying removing & restoring supply the same & making good the damages etc as reqd.	3.00	Nos.		
15	Dismantling and refixing of wooden board of any sizess on surface or in recessed etc as reqd.	4.00	Nos.		
16	Dismantling & refixing brass compression type cable gland 25 sq.mm to 400 sq.mm. cable.	1.00	Nos.		
17	Dismantling and refixing of M.S./PVC box of up to 250 x 300 x100 on surface recessed as required. including painting with enamel paint as reqd	3.00	Nos.		
18	Lifting & removing cable of following sizes from trenches or clamped on surface, making roll depositing the same in the store I/c cartage etc as reqd.				
18.1	up to 35 sq.mm.	18.00	Mtr.		

S.No	Description	Qty	Unit	Rate	Amount
------	-------------	-----	------	------	--------

(In words & Figures)

19 Supply, Installation, testing & commissioning of AC ceiling fan of following sweep 220 volts without regulator I/c wiring the down rods of standard length up to 30 cm with 1.5 sq.mm. PVC insulated copper conductor single core cable etc as reqd.

19.1 1200 mm 2.00 Nos

20 Supplying, fixing, connecting, testing & commissioning 10-60A, single phase meter( Cat no. SPPB152A111000OC01, HPL make) 230V, 50 hz, digital LCD type electronic kWh electronic meter i/c sealing the same (sealing material will be supplied by the dept.) Gurantee car having serial no. of the meter to be submitted in the dept. etc. as reqd. 4.00 Nos.

21 Supplying, fixing, connecting, testing & commissioning 100/5A, CT operated LCD display three phase 415Volt, 50 hz, LCD multifunction meter 3PH 4W 240V 5A Cat No. WR301BC3C00 (Make: HPL or L&T or its equivalent) i/c sealing the same (sealing material will be supplied by the dept.) etc. as reqd. 2.00 Nos.

Total Rs

\_\_\_\_\_



अविभागीय अभियंता (वि.वि.) E.E. (Elect.  
सुंनिताकि, माऊवरी संस्थान, कानपुर  
W.D., I.L.T., Kanpur

३