

## QUOTATION

Name of work -: Repairing & replacement of defective switch/ socket, casing & capping , distribution boards etc. at House no-646, 655, 611, 659, 606, 628, 670, 484, 4094, 642, 666, 4098, 4081, 4094, Old RA 101, 217, 114 RA Tower D-102, 304, 402, 408, 308, S-620, 106, 308, RA S-325, 213, 523, 130, 511, 426, 108, 322, 147, 236, 132, Old RA 110, 216, type-IV- 662, 641, 475, 480, 4093, 4068, 668 etc. north side drive residences as per enclosed complaints at IIT Kanpur.

S.No	Description	Qty	Unit	Rate	Amount
1	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable and 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel conduit including dismantling as required.				
1.1	Group B	8.00	Points		
2	Supplying & drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel / PVC conduit as reqd.				
2.1	1 x 1.5 Sq.mm..	34.00	Mtr.		
2.2	3 x 1.5 Sq.mm..	64.00	Mtr.		
2.3	3 x 2.5 Sq.mm..	67.00	Mtr.		
2.4	3 x 4 Sq.mm..	13.00	Mtr.		
3	Supply and fixing of following sizes of medium class PVC conduit along with the accessories in surface /recess including cutting the wall and making good the same in case of recessed conduit as reqd.				
3.1	20mm	15.00	Mtr		
4	Supplying and fixing following piano type switch /socket on existing switch box/cover I/c connection etc as reqd.				
4.1	5/6 Amp switch	24.00	Nos.		
4.2	2 way 5/6 amp switch	1.00	Nos.		

S.No	Description	Qty	Unit	Rate	Amount
4.3	15/16 Amp. switch	1.00	Nos.		
4.4	3 Pin 5/6 Amp. socket outlet	6.00	Nos.		
4.5	6 Pin 15/16 Amp. socket outlet.	1.00	Nos.		
4.6	bell push	1.00	Nos.		
4.7	Fan regulator socket type rotary/dimmer	3.00	Nos.		
5	Supply, fixing, following modular type switch / socket on existing modular plate & switch box including connectins but excluding modular plate etc. as reqd.				
5.1	5/6 Amp switch	4.00	Nos.		
5.2	15/16 Amp. switch	11.00	Nos.		
5.3	3 Pin 5/6 Amp. socket outlet	1.00	Nos.		
5.3	6 Pin 15/16 Amp. socket outlet.	12.00	Nos.		
5.4	Fan regulator socket type rotary step	6.00	Nos.		
6	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.				
6.1	1/2 module	1.00	Nos.		
6.2	3 module	1.00	Nos.		
6.3	4 module	2.00	Nos.		
6.4	6 module	1.00	Nos.		
7	Supplying and fixing following modular base & cover plate on existing modular metal boxes etc. as reqd.				
7.1	1 or 2 module	1.00	Nos.		

S.No	Description	Qty	Unit	Rate	Amount
7.2	3 module	6.00	Nos.		
7.3	6 module	5.00	Nos.		
8	Supplying and fixing brass batten/ angle holder including connection etc. as required.	9.00	Nos.		
9	Supplying and fixing call bell/ buzzer suitable for single phase, 230 V, complete as required.	1.00	Nos.		
10	Drawing of optical cable enhanced cat 5/cat 6/telephone/ networking /power cable in existing steel conduit pipe/GI /HDPE pipe including numbering of networking wire from room to rack as reqd.	95.00	Mtr.		
11	Providing and fixing following sizes of PVC casing and capping on surface as reqd.				
11.1	20 x 12 mm	106.00	Mtr.		
11.2	25 x 16 mm	40.00	Mtr.		
11.3	32x 16 mm	14.00	Mtr.		
12	Supplying and fixing wooden board of following sizes on surface or in recessed with suitable size of phenolic laminated sheet cover in the front etc as reqd.				
12.1	100 mm x 100 mm	4.00	Nos.		
13	Supply and fixing and connecting & commissioning following CFL / lamps in existing fitting as reqd.(Make- Phillips or its equivalent)				
13.1	LED tube light 18 / 20 Watt.	1.00	Nos.		
14	Supply / fixing , testing & commissioning of 12W LED. Slim surface mounted round LED panel al. die cast body with premium diffuser to ensure glare free as required complete etc as reqd	24.00	Nos.		

