

## QUOTATION

**Name of work:-** Repairing of secondary service cable going from Substation No. 5 to New sports complex and Substation No. 8 to Hall-8.

S.N	Description of item	Qty	Unit	Rate	Amount
(In words & Condition)					
1	Supplying and making straight through joint with heat shrinkable kit including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.				
a	3½ X 300 sq. mm	2.00	Each		
b	3½ X 400 sq. mm	2.00	Each		
2	Dismantling and refixing brass compression type gland up to 400 sq. mm. cable	4.00	Nos		
3	Locating fault in the cable lines with fault locator machine etc and rectifying removing & restoring the same and making good the damages etc as required.	4.00	Nos.		
4	Digging cable trench for taking out cable and refilling , watering ,ramming the sameafter taking out cable as reqd complete.	30.00	Mtr		
5	Lifting removing cable exceeding 35 sq.mm. but not exceeding 95sq.mm. size from trench/clamps, making role & depositing the same in store l/c cartage.	30.00	Mtr		

**Total Rs.**

  
अधिकाारी अधियता (वि०) E.E. (Elect.  
सं० वि० वि०) नारायण संस्थान, कानपुर  
I.W.D., I.I.T., Kanpur  
